

LOCATION MAP

PROJECT HORIZONTAL DATUM

HORIZONTAL CONTROL DATA IS BASED ON REAL TIME GPS/GNSS NETWORK OBSERVATIONS PROVIDED BY CALIFORNIA DRAFTING AND SURVEY SUPPLY. CALIFORNIA COORDINATE SYSTEM ZONE III, NAD83 DATUM EPOCH 2012

PROJECT BENCHMARK

ELEV DATUM:

VERTICAL CONTROL DATA IS BASED ON CUPERTINO CITY BENCHMARK NUMBER 4 BEING A CONCRETE NAIL IN TOP OF CURB NORTHEAST RETURN ON STEVENS CREEK BOULEVARD @ PORTAL AVENUE. ELEVATION TAKEN AS


THIS TOPOGRAPHIC SURVEY WAS DONE BY A FIELD CREW UNDER THE SUPERVISION

OF ALEXANDER FONG, PLS 9252, JULY 10, 2018.

BIKE BOULEVARD IMPROVEMENTS PHASE 1

CUPERTINO, CALIFORNIA

PROJECT NO. 2017-01.05



SITE MAP

SHEET INDEX

SHEET NO. TITLE

C1 TITLE SHEET

C2 LEGENDS, NOTES, AND ABBREVIATIONS

C3 CIVIL DETAILS

C4 CIVIL DETAILS

C5 DEMOLITION PLAN

C6 IMPROVEMENT PLAN - NORTH PORTAL AVENUE FROM STEVENS CREEK BLVD. TO WHEATON DR. (LOCATION 1)

C7 IMPROVEMENT PLAN - NORTH PORTAL AVENUE AT AMHERST DRIVE (LOCATION 1)

C8 IMPROVEMENT PLAN - MERRITT DRIVE AT VISTA DRIVE (LOCATION 1)

C9 IMPROVEMENT PLAN - GREENLEAF DRIVE AT BEARDON DRIVE (LOCATION 5)

IMPROVEMENT PLAN - BANDLEY DRIVE AT MARIANI AVENUE (LOCATION 5)

C11 GRADING PLAN - BANDLEY DRIVE AT MARIANI AVENUE (LOCATION 5)

C12 IMPROVEMENT PLAN - TORRE AVENUE AT TOWN CENTER LANE (LOCATION 3)

C13 SPEED TABLES

C14 SPEED TABLES

SS-1 SIGNING AND STRIPING NOTES, LEGEND, AND DETAILS

SIGNING AND STRIPING IMPROVEMENTS N. PORTAL AVE. FROM STEVENS CREEK BLVD. TO AMHERST DR. (LOCATION 1

SS-3 SIGNING AND STRIPING IMPROVEMENTS N. PORTAL AVE. AND AMHERST DR. (LOCATION 1)

SS-4 SIGNING AND STRIPING IMPROVEMENTS N. PORTAL AVE. FROM AMHERST DR. TO MERRITT DR. (LOCATION 1)

S-5 SIGNING AND STRIPING IMPROVEMENTS MERRITT DR. FROM PORTAL AVE. TO N. BLANEY AVE. (LOCATION

SS-6 SIGNING AND STRIPING IMPROVEMENTS MERRITT DR. FROM N. BLANEY AVE. TO RANDY LN. (LOCATION 1)

SS-7 SIGNING AND STRIPING IMPROVEMENTS MERRITT DR. FROM VISTA DR. TO LARRY WAY (LOCATION 1)

SS-8 SIGNING AND STRIPING IMPROVEMENTS BANDLEY DR. AND MARIANI AVE. (LOCATION 5)

SS-9 SIGNING AND STRIPING IMPROVEMENTS BEARDON DR. AND GREENLEAF DR. (LOCATION 5)

S-10 SIGNING AND STRIPING IMPROVEMENTS GREENLEAF DR. FROM BEARDON DR. TO GLENCLOE DR. (LOCATION 5)

S-11 SIGNING AND STRIPING IMPROVEMENTS GREENLEAF DR. FROM GLENCOE DR. TO FLORA VISTA AVE. (LOCATION 5)

SS-12 SIGNING AND STRIPING IMPROVEMENTS GREENLEAF DR. FROM FLORA VISTA AV. TO ANN ARBOR AVE. (LOCATION 5)

SS-13 SIGNING AND STRIPING IMPROVEMENTS GREENLEAF DR. FROM ANN ARBOR AVE. TO CASTINE AVE. (LOCATION 5)

S1 STRUCTURAL PLAN AND DETAILS - GREENLEAF DRIVE AT BANDLEY DRIVE AND MARIANI AVENUE

L1 LANDSCAPE NOTES AND PLANT LIST

L2 PLANTING PLAN - TORRE AVENUE AT TOWN CENTER LANE

L3 CONSTRUCTION DETAILS

L4 IRRIGATION PLAN - TORRE AVENUE AT TOWN CENTER LANE

CITY OF CUPERTINO BEST MANAGEMENT PRACTICES

L5 IRRIGATION NOTES AND LEGEND

L6 IRRIGATION DETAILS

L7 IRRIGATION DETAILS

L8 IRRIGATION DETAILS

APPROVED BY:

ROGER LEE
ACTING DIRECTOR OF PUBLIC WORKS

3/21/2019

DATE

DATE

FOR CITY OF CUPERTINO USE



UNAUTHORIZED CHANGES & USES: THE ENGINEER PREPARING THESE PLANS WILL NOT BE RESPONSIBLE FOR, OR LIABLE FOR, UNAUTHORIZED CHANGES TO OR USES OF THESE PLANS. ALL CHANGES TO THE PLANS MUST BE IN WRITING AND MUST BE APPROVED BY THE PREPARER OF THESE PLANS.

Bellecci & Associates, inc.

Civil Engineering • Land Surveying

7077 Koll Center Pkwy, Suite 210 Pleasanton, CA 94566
Phone (925) 681-4885

	Date:						PROFESSIONAL
	Scale:						
•	Designed:						E CO / N N N N N N N N N N N N N N N N N N
	Drawn:						N P R
	Checked:						No. 76008 /★//
	Proj. Engr:	REVISIONS	DESIGN	DESIGN	CITY	APPR.	STATE CIVIL ORNIT
	File:	TAL VIOLOTAG	BY	DATE	APPR.	DATE	OF CALIFOR

IMPROVEMENT PLANS FOR

BIKE BOULEVARD IMPROVEMENTS PHASE 1

PUBLIC WORKS INSPECTOR: VOICE MAIL: REVIEWED BY: CITY OF CUPERTINO

CUPERTINO CALIFOI

CALIFORNIA

SHEET **1** OF **37**

LE	EGEND			
P	ELECTRIC BOX		WOODEN FEN	CF
GM	GAS METER	——×——×—	CHAIN LINK I	
\bowtie	GAS VALVE			
-	MISC SIGN		RIGHT OF WA	A Y
⊚	SANITARY SEWER CLEANOUT	-	WALL	
(3)	SANITARY SEWER MANHOLE	OH	OVERHEAD LI	NE
\oslash	STORM DRAIN THROUGH CURB	0 0 0 0	GUARD RAIL	
	STORM DRAIN CATCHBASIN		LANE STRIPIN	1G
(D)	STORM DRAIN MANHOLE			
À	SURVEY SET 60D NAIL	. △ _A .		
●	SURVEY MONUMENT	Δ	CONCRETE H	ATCH
	SURVEY CUT X			
0	SURVEY IRON PIPE		PAVEMENT H	ATCH
•	SURVEY REBAR			
×	SURVEY NAIL & TAG			
○	SURVEY SET REBAR	ELEVATION		
_	TELEPHONE BOX		GRADING ELE	EVATION
	TELEPHONE MH	0		
$\overline{\bigcirc}$	UTIL JOINT POLE	Λ Т 0. Т		AT&T
	UTIL MH	———— AI&I		AT&T
т Д	UTIL STREET LIGHT UTIL STREET LIGHT POLE			
•	WATER HYDRANT	—— Е ——	— Е ———	PG&E ELECTRIC
₩M	WATER HIDRANT WATER METER			
<u>w</u> m	WATER VALVE		C ———	COMCAST
_	DUCTILE IRON DOME	C	C	3 S.M. S. (13)
	DOCTILE INON DOME			
		MCI		VERIZON
		SD -		STORM DRAIN
				STORM BRAIN
			- SS ———	CUPERTINO SANITARY DIST
		\ <i>\</i> /		CALWATER OR
		W		SAN JOSE WATER COMPAN
		——— JT ———	– JT ———	JOINT TRENCH
		G		PG&E GAS
		-		

ABBREVIATIONS LATERAL LIP OF GUTTER AGGREGATE BASE AREA DRAIN BEGIN CURVE BLOWOFF VALVE BOTTOM OF WALL OW POINT RIGHT PUBLIC UTILITY EASEMENT PUBLIC SERVICE EASEMENT POLYVINYL CHLORIDE BACK OF WALK CURB & GUTTER CATCH BASIN RELATIVE COMPACTION REINFORCED CONCRETE PIPE RIGHT OF WAY URB RAMP STORM DRAIN MANHOLE DUCTILE IRON PIPE EASEMENT STANDARD DIMENSION RATIO SANITARY SEWER SANITARY SEWER CLEAN OUT SANITARY SEWER MANHOLE DGE OF PAVEMENT WALK SANITARY SEWER LATERAL SIDEWALK TOP OF CURB TOP OF CURB RAMP AŠPHĀLT CONCRETE THEORETICAL FLOW LINE FIRE HYDRANT WATER METER WATER SERVICE WATER VALVE CROSSING GRADE BREAK

SITE LOCATION SUMMARY

LOCATION 1:

N. PORTAL AVE. FROM STEVENS CREEK BLVD. TO WHEATON DR. N. PORTAL AVENUE AT AMHERST DRIVE MERRITT DRIVE AT VISTA DRIVE

LOCATION 3:

TORRE AVENUE AT TOWN CENTER LANE

LOCATION 5:

GREENLEAF DRIVE AT BEARDON DRIVE BANDLEY DRIVE AT MARIANI AVENUE

CITY OF CUPERTINO **BIKE BOULEVARD IMPROVEMENTS PHASE 1** SITE STAGING AND WORKING DAYS CHART Number of Calendar Days to Latest End Date for All Contract complete AC and Concrete Work **Earliest Start Date for demolition** Site Location Location # Work completion and Temporary Striping after first day of Demolition June 8, 2019 21 N. Portal Ave and Amherst Dr August 14, 2019 Merritt Dr and Vista Dr June 8, 2019 21 August 14, 2019 Mariani Ave and Bandley Dr June 8, 2019 August 14, 2019 21 Complete all the contract work per After the completion of "Mariani Torre Ave and Town Center Ln the number of days indicated in 21 Ave and Bandley Dr" the specifications. Complete all the contract work per N. Portal Ave between Stevens Creek Blvd | After the completion of "N. Portal the number of days indicated in 14 and Wheaton Dr Ave and Amherst Dr" the specifications. Complete all the contract work per After the completion of "Merritt Greenleaf Dr and Beardon Dr the number of days indicated in 21 Dr and Vista Dr" the specifications. Complete all the contract work per Others All other remaining work After August 14, 2019 the number of days indicated in the specifications.

CITY OF CUPERTINO GENERAL NOTES

- 1. ALL WORK SHALL BE IN ACCORDANCE WITH THE STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS (LATEST EDITION, AS AMENDED), AND STANDARD PLANS (LATEST EDITION, AS AMENDED), AND CITY OF CUPERTINO STANDARD DETAILS. THE CONTRACTOR SHALL PERFORM THE WORK DESCRIBED IN THE SPECIFICATION, AND AS SHOWN ON THE DRAWINGS, AND TO THE SATISFACTION OF THE CITY ENGINEER.
- 2. APPROVAL OF THESE PLANS SHALL NOT RELEASE THE CONTRACTOR OF THE RESPONSIBILITY FOR CORRECTIONS OF MISTAKES, ERRORS, OR OMISSIONS CONTAINED THEREIN. IF DURING THE COURSE OF CONSTRUCTION OF IMPROVEMENTS, PUBLIC INTEREST REQUIRES A MODIFICATION OF/OR A DEPARTURE FROM THE CITY OF CUPERTINO STANDARD DETAILS OR THESE IMPROVEMENTS PLANS, THE CITY ENGINEER SHALL HAVE THE AUTHORITY TO REQUIRE SUCH MODIFICATION OR DEPARTURE AND TO SPECIFY THE MANNER IN WHICH THE SAME IS TO BE COMPLETED, AT THE SOLE EXPENSE OF THE CONTRACTOR.
- 3. APPROVAL OF THESE PLANS BY THE CITY ENGINEER IS ONLY FOR PUBLIC RIGHT-OF-WAY IMPROVEMENTS (INCLUDING STORM DRAIN IN THE RIGHT OF WAY), AND NOT FOR WATER, SEWER OR DRY UTILITIES. IT IS THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE REVIEWS AND APPROVAL FROM EACH OF THE UTILITY COMPANIES, AND TO PROVIDE APPROVAL LETTERS AS REQUESTED.
- 4. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO ENSURE THE APPROVED PLANS OR THE LATEST REVISED PLANS ARE FURNISHED TO ITS SUBCONTRACTORS, AND TO ENSURE THE LATEST APPROVED PLANS ARE ONSITE AT ALL TIMES DURING CONSTRUCTION.
- 5. THE CONTRACTOR SHALL NOTIFY THE CITY OF CUPERTINO PUBLIC WORKS INSPECTOR TWO (2) WORKING DAYS PRIOR TO REQUIRING AN INSPECTION. CALL (408) 777-3104 TO SCHEDULE PUBLIC WORKS INSPECTIONS.
- 6. CONSTRUCTION AREA TRAFFIC CONTROL DEVICES SHALL BE INSTALLED PRIOR TO BEGINNING OF WORK.
- 7. NOTIFY CITY OF CUPERTINO TRAFFIC SIGNAL MAINTENANCE FOR INSPECTION OF TRAFFIC SIGNAL FACILITY FOUNDATION EXCAVATIONS AT (408) 777-1366, TWO (2) WORKING DAYS PRIOR TO POURING ANY CABINET OR SIGNAL FOUNDATIONS RELATING TO THE JOB.
- 8. THE CONTRACTOR SHALL LOCATE UNDERGROUND FACILITIES IN THE AREA OF WORK. THE CONTRACTOR SHALL CONTACT UNDERGROUND SERVICE ALERT (USA) AT 811 TWO (2) WORKING DAYS IN ADVANCE OF ANY WORK FOR LOCATION OF THE UNDERGROUND FACILITIES.
- 9. ALL UNDERGROUND UTILITIES SHALL BE INSTALLED AND BACKFILLED BEFORE PLACEMENT OF THE BASE MATERIAL AND SURFACE STRUCTURES. IF UTILITIES ARE TO BE INSTALLED SUBSEQUENTLY, A WRITTEN NOTIFICATION FROM THE AFFECTED UTILITY COMPANY INDICATING ITS COMMITMENT TO BORE OR TUNNEL SHALL BE SUBMITTED TO THE CITY ENGINEER BEFORE PROCEEDING WITH THE WORK. UNDERGROUND UTILITIES, EXCEPT STORM DRAINS AND SANITARY SEWERS, SHALL NOT BE PERMITTED IN PAVEMENT AREA, WITH THE EXCEPTION OF STREET CROSSINGS, UNLESS APPROVED BY THE CITY ENGINEER.
- 10. ALL WATER LINES, VALVES, HYDRANTS, AND APPURTENANCES THERETO INSTALLED WITHIN THE PUBLIC RIGHT-OF-WAY SHALL BE THE PROPERTY OF THE UTILITY
- 11. STORM DRAIN LINES INSTALLED AS PART OF THE WORK ON THESE PLANS SHALL BE CLEARED OF ALL DEBRIS AND OBSTRUCTIONS PRIOR TO FINAL ACCEPTANCE.
- 12. ALL TRENCH BACKFILL, FILL AREAS, AND BASE MATERIAL SHALL ATTAIN A MINIMUM 95% RELATIVE COMPACTION. FOR TYPICAL TRENCH SECTIONS, EXCEPT FOR SANITARY SEWERS, REFER TO THE CITY STANDARD DETAILS.
- 13. THE CONTRACTOR SHALL PAY ALL COSTS FOR MOISTURE-DENSITY CURVES (CALIF. TEST NO. 216E) AND ANY OTHER TESTS REQUIRED BY THE CITY ENGINEER
- 14. TRENCH PLATES IN THE TRAVELED WAY SHALL BE TRAFFIC RATED, NO MOVEMENT OR NOISE, PROPERTY SECURED AND SHALL BE RECESSED.
- 15. ALL TRENCHES LOCATED WITHIN 5' OF THE EDGE OF PAVEMENT (IE. CURB, LIP OF GUTTER, EDGE OF PAVEMENT, ETC.) SHALL BE REPAVED TO THE EDGE OF PAVEMENT.
- 16. ALL NEW PAVEMENT SHALL MATCH THE EXISTING PAVEMENT SECTION.
- 17. EXISTING PAVEMENT THAT IS REMOVED OR DAMAGED SHALL BE REPLACED AS REQUIRED BY THE CITY ENGINEER
- 18. MANHOLE FRAMES AND COVERS SHALL BE BROUGHT TO FINISH GRADE PRIOR TO FINAL ACCEPTANCE.
- 19. FIVE (5) WORKING DAYS PRIOR TO INSTALLING PERMANENT STRIPING, THE CONTRACTOR SHALL CAT TRACK THE STRIPING AND REQUEST REVIEW OF THE CAT TRACKS BY THE CITY TRAFFIC ENGINEER. THE CITY ENGINEER SHALL HAVE THE RIGHT TO MAKE CHANGES IN THE LOCATION OF THE ALIGNMENT OF TRAFFIC STRIPES, PAVEMENT MARKINGS, AND PAVEMENT MARKERS.
- 20. CONCRETE FOR USE IN ALL CONCRETE STRUCTURES SHALL CONFORM TO CALIFORNIA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS SECTION 90. DROP INLETS, SIDEWALKS, CURBS AND GUTTERS SHALL CONTAIN 590 LBS. OF CEMENT PER CUBIC YARD AND SHALL ATTAIN A MINIMUM STRENGTH OF 4,000 PSI IN 28 DAYS.
- 21. DROP INLETS SHALL BE CONSTRUCTED CONFORMING TO CITY STANDARD DETAILS UNLESS OTHERWISE NOTED ON THE PLANS. DROP INLETS SHALL BE INSTALLED CONCURRENT WITH THE CONSTRUCTION OF THE CURB AND GUTTER. "NO DUMPING FLOWS TO THE BAY." PLAQUE SHALL BE INSTALLED ON THE CURB ADJACENT
- 22. A MINIMUM THICKNESS OF FIVE (5) INCHES OF CONCRETE SHALL BE REQUIRED FOR COMMERCIAL DRIVEWAY APPROACHES AND FOUR (4) INCHES FOR RESIDENTIAL. THE DRIVEWAY APPROACH SHALL BE INSTALLED CONCURRENT WITH THE CONSTRUCTION OF THE CURB AND GUTTER.
- 23. ONE POUND OF DISPERSING BLACK SHALL BE MIXED WITH EACH CUBIC YARD OF CONCRETE AT THE BATCH PLANT.
- 24. CITY STANDARD STREET LIGHTS SHALL BE INSTALLED AS REQUIRED BY THE DIRECTOR OF PUBLIC WORKS, AND SHALL CONFORM TO THE CITY STANDARD DETAILS AND NOTES. DURING CONSTRUCTION OPERATIONS, TEMPORARY STREET LIGHTING SHALL BE PROVIDED AS NECESSARY TO ENSURE THE PUBLIC SAFETY. TEMPORARY STREET LIGHTS SHALL BE INSTALLED AT THE DISCRETION OF, AND TO THE SATISFACTION OF, THE DIRECTOR OF PUBLIC WORKS.
- 25. NEW CITY STANDARD STREET MONUMENTS AND OTHER PERMANENT MONUMENTS DISTURBED DURING CONSTRUCTION SHALL BE REPLACED BEFORE ACCEPTANCE OF THE IMPROVEMENTS BY THE CITY ENGINEER. ATTENTION IS DIRECTED TO SECTION 8771 OF THE CALIFORNIA BUSINESS AND PROFESSIONS CODE FOR THE REQUIREMENTS CONCERNING SURVEY MONUMENTS. EXISTING SURVEY MONUMENTS SHALL BE LOCATED AND REFERENCED BY OR UNDER THE DIRECTION OF A LICENSED LAND SURVEYOR OR REGISTERED CIVIL ENGINEER PRIOR TO CONSTRUCTION OPERATIONS, AND A CORNER RECORD OR RECORD OF SURVEY SHALL BE FILED WITH THE COUNTY SURVEYOR OF THE COUNTY OF SANTA CLARA. EXISTING SURVEY MONUMENTS SHALL BE RESET TO FINISH GRADE, AND A CORNER RECORD OR RECORD OF SURVEY SHALL BE FILED WITH THE COUNTY SURVEYOR OF THE COUNTY OF SANTA CLARA PRIOR TO THE RECORDING OF THE CERTIFICATE OF COMPLETION FOR THE PROJECT.
- 26. CONSTRUCTION SURVEY STAKES OR MARKS (CONTROL STAKES) TO ESTABLISH LINES AND GRADES SHALL BE SET BY THE CONTRACTOR'S LICENSED LAND SURVEYOR.
- 27. NOTIFY THE CITY INSPECTOR TWO (2) WORKING DAYS IN ADVANCE OF REQUIRING SERVICES FOR CHECKING FIELD STAKING. THREE (3) COPIES OF THE CUT SHEETS SHALL BE FURNISHED TO THE CITY INSPECTOR.
- 28. CONTRACTOR IS RESPONSIBLE FOR DUST CONTROL AND ENSURING THE AREA ADJACENT TO THE WORK IS LEFT IN A CLEAN CONDITION.
- 29. CONTRACTOR SHALL REVIEW CITY DETAIL 6-4 ON TREE PROTECTION PRIOR TO ACCOMPLISHING ANY WORK OR REMOVING ANY TREES.
- 30. UTILIZE BEST MANAGEMENT PRACTICES (BMP'S), AS REQUIRED BY THE STATE WATER RESOURCES CONTROL BOARD, FOR ANY ACTIVITY, WHICH DISTURBS THE SOIL. SEE SHEET C15

				0)227700	IMPRO	VEMENT PLANS FOR
	Date:			REDDINAL	.,,,,	
Pollogoi 9 Aggoriates inc	Scale:			LEGIN AND AND AND AND AND AND AND AND AND AN	BIKE BOULEVARD	IMPROVEMEN
Bellecci & Associates, inc.	Designed:			NEGO.		
Civil Engineering ● Land Surveying	Drawn:				LEGENDS, NO	TES. AND ABE
7077 Koll Center Pkwy, Suite 210 Pleasanton, CA 94566 Phone (925) 681–4885	Checked:			No. 76008 /★	,	,
www.bellecci.com	Proj. Engr:	REVISIONS	DESIGN DESIGN CITY A BY DATE APPR. D	PPR. SAIR OF SHIP		
	File:	REVISIONS	BY DATE APPR. D	DATE OF CALLES	CUPERTINO	CALIFORNIA

FOR

JENTS - PHASE 1 **ABBREVIATIONS**


PROJECT # <u>2017-01.05</u> PUBLIC WORKS INSPECTOR: VOICE MAIL: REVIEWED BY:

FOR CITY OF CUPERTINO USE



CITY OF **CUPERTINO**

SHEET **2** OF **37**



1. Prior to any construction operations contractor shall construct and maintain, for each protected tree on a construction site, a protective fencing which encircles the outer limits of the critical root zone (CRZ) of the tree to protect it from construction activity. The CRZ is calculated 1.25 feet times the diameter of the trunk measured in inches 4.5 feet above the natural grade).

- 2. All protective fencing shall be in place prior to commencement of any site work and remain in place until all exterior construction activity at the site has been completed.
- 3. Protective fencing shall be at least six (6) feet high, clearly visible, and shall have a tree protection sign affixed to the fence every twenty (20) feet in such a manner to be clearly visible and legible to workers on the site at a distance of twenty-five (25) feet. The sign(s) shall read "Tree Protection Zone Keep out".
- 4. The owner shall cause the required fencing and signage to be installed and maintained for the duration of the construction. 5. In situations where a protected tree remains in the immediate area of intended construction and the tree may be in danger of being damaged by


construction equipment or other activity, the contractor or subcontractor shall protect the tree with 2"x4" lumber encircled with wire or other


- means that do not damage the tree. The intent is to protect the trunk of the tree against incidental contact by large construction equipment. 6. Material Storage: No storage or placement of materials intended for use in construction or waste materials accumulated due to excavation or demolition shall be placed within the limits of the critical root zone of any protected tree.
- 7. Equipment Cleaning/Liquid Disposal: No equipment shall be cleaned or other liquids, including, without limitation, paint, oil, solvents, asphalt, concrete, mortar or similar materials deposited or allowed to flow into the critical root zone of a protected tree.
- 8. Tree Attachments: No signs, wires or other attachments, other than those of a protective nature, shall be attached to any protected tree. 9, Vehicular Traffic; No vehicular and/or construction equipment traffic or parking shall take place within the critical root zone of any protected
- 10. No heavy equipment, including but not limited to trucks, tractors, trailers, bulldozers, excavators, skid steer tractors, trenchers, compressors, and hoists, shall be allowed inside the drip-line of any protected tree on any construction site.
- 11. Grade Changes: No grade changes shall be allowed within the limits of the critical root zone of any protected tree unless adequate protective construction methods are approved in advance in writing by the city.
- 12. Impervious Paving: No paving with asphalt, concrete or other impervious materials shall be placed within the limits of the critical root zone of a protected tree, unless expressly permitted by the public works Dept
- 13, Root Pruning: All roots two inches or larger in diameter which are exposed as a result of trenching or other excavation shall be cut off square
- with a sharp medium tooth saw and covered with natural fiber burlap within two hours of initial exposure. 14. All public sidewalks shall remain open, free and clear for public access, unless closure is permitted by the Public Works Department.


TREE PROTECTION STANDARDS


REVISED 5/13













Civil Engineering • Land Surveying 7077 Koll Center Pkwy, Suite 210 Pleasanton, CA 94566 Phone (925) 681-4885 www.bellecci.com

Checked: Proj. Engr: DESIGN DESIGN CITY APPR. DATE REVISIONS File:

BIKE BOULEVARD IMPROVEMENTS - PHASE 1

CALIFORNIA

IMPROVEMENT PLANS FOR

CIVIL DETAILS CUPERTINO

FOR CITY OF CUPERTINO USE

PUBLIC WORKS INSPECTOR:


VOICE MAIL:


REVIEWED BY:





CITY OF **CUPERTINO C3**

SHEET **3** OF **37**












REVISIONS



IMPROVEMENT PLANS FOR

BIKE BOULEVARD IMPROVEMENTS - PHASE 1
CIVIL DETAILS

CALIFORNIA

CUPERTINO

FOR CITY OF CUPERTINO USE
PROJECT # __2017-01.05

PUBLIC WORKS
INSPECTOR:
VOICE MAIL:
REVIEWED BY:



CITY OF CUPERTINO

C4

SHEET 4 OF 37

CUPERTINO

CALIFORNIA

DATE

CUPERTINO

CALIFORNIA

SHEET **7** OF **37**

DESIGN DESIGN CITY APPR. DATE


REVISIONS

www.bellecci.com

Proj. Engr:

File:

REVISIONS



CONSTRUCTION NOTES

- CONSTRUCT NEW CONCRETE SIDEWALK AND BASE PER CITY STD. DETAIL 1-19. DOWEL INTO EXISTING PER CITY STD. DETAIL 1-23
- CONSTRUCT NEW CONCRETE CURB & GUTTER PER CITY STD. DETAIL 1-16 (A2-6); CURB HEIGHT VARIES SEE GRADING PLAN
- INSTALL TRUNCATED DOMES ON 4" THICK CONCRETE SUBSLAB OVER 4" THICK CLASS 2 AB, COMPACTED TO 95% R.C.
- INSTALL 12 LF OF 12" PVC SDR-26 AT 1% SLOPE; TRENCH BACKFILL PER CITY STD. DETAIL 4-24
- 5 INSTALL 24 LF OF 12" PVC SDR-26 AT 1% SLOPE; TRENCH BACKFILL PER CITY STD. DETAIL 4-24
- 6 INSTALL 40 LF OF 12" PVC SDR-26 AT 1% SLOPE; TRENCH BACKFILL PER CITY STD. DETAIL 4-24
- CONNECT NEW 12" PVC SDR-26 TO EXISTING SDMH
- REMOVE EXISTING STORM DRAIN INLET & CONSTRUCT NEW SDMH PER CITY STD. DETAIL
- (9) CONSTRUCT NEW SDMH OVER EXISTING STORM DRAIN PIPE
- INSTALL STANDARD DROP INLET CURB OPENING PER CITY STD. DETAIL 3-2
- \$\langle 11 \rangle SAWCUT LINE
- 10" THICK FULL-DEPTH ASPHALT CONCRETE (FDAC)
- CONSTRUCT RAISED ASPHALT CONCRETE CROSSWALK. WEDGE GRIND PERIMETER OF RAISED CROSSWALK AREA 2" THICK MINIMUM (SEE DEMOLITION PLAN). OVERLAY ASPHALT CONCRETE TO NEW GRADES. THICKNESS OF AC OVERLAY VARIES BETWEEN 2" AND 6" THICK
- INSTALL 4" THICK DECOMPOSED GRANITE OVER 3" THICK CLASS 2 AB, COMPACTED TO 95% R.C.
- INSTALL 9 LF OF 12" PVC SDR-26 AT 1% SLOPE;
- TRENCH BACKFILL PER CITY STD. DETAIL 4-24
- PROTECT IN PLACE EXISTING CHAIN LINK FENCE
- PROTECT IN PLACE EXISTING ARTIFICIAL TURF
- PROTECT IN PLACE EXISTING CONCRETE SIDEWALK
- PROTECT IN PLACE EXISTING LANDSCAPING AND IRRIGATION SYSTEM CONSTRUCT CASE G CURB RAMP PER CALTRANS STD. PLAN A88A OVER 4"
- THICK CLASS 2 AB, COMPACTED TO 95% R.C.
- PROTECT IN PLACE EXISTING WATER VALVE
- CONSTRUCT CASE F CURB RAMP PER CALTRANS STD. PLAN A88A OVER 4" THICK CLASS 2 AB, COMPACTED TO 95% R.C.
- TRANSITION FROM 6" CURB TO APPROXIMATE 4" ROLLED CURB 3' LONG (MEASURED AS PART OF CURB & GUTTER LF)

CALIFORNIA

- SWALE
- 6"X6" CONCRETE HEADER (DOWEL INTO CONCRETE SIDEWALK AND CONCRETE CURB)
- PROTECT IN PLACE EXISTING STREET LIGHT & CONCRETE FOUNDATION
- BACKFILL GAP CREATED BY DEMOLITION OF EXISTING SIDEWALK

	0.02	868 66 66 5	0110
128	10.12'	S89° 00' 35"E°	C149
130	9.34'	N60° 59' 25"E°	C135
132	0.47	S89° 00' 23"E°	C134
144	3.91'	N89° 13' 00"W°	C133
146	9.45'	N59° 00' 35"W°	C132
148	3.66'	N89° 00' 35"W°	C150
150	2.85'	S00° 58′ 32″W°	C151
152	9.39'	S29° 01' 28"E°	C152
154	5.25'	S00° 51′ 56″W°	C145
157	15.15'	S87° 59′ 36″W°	C144
160	15.72'	N02° 37' 41"E°	C143
163	13.78'	S00° 40' 07"W°	C142

9.15' S64° 37' 49"E°

Direction

4.30' S89' 00' 35"E'

9.32' S59° 00' 35"E°

| Curve # | Length | Radius | Delta

C148

C141

4.56' | 3.00' | 87.00°

11.89' | 30.39' | 22.40°

11.84' | 7.50' | 90.43'

2.62' | 5.00' | 30.00°

2.62' | 5.00' | 30.00°

2.62' 5.00' 30.00°

2.62' | 5.00' | 30.00°

12.28' | 24.40' | 28.84°

4.61' | 5.00' | 52.84°

2.19' | 5.00' | 25.13'

2.61' | 5.00' | 29.89*

2.62' | 5.00' | 30.00°

23.57' | 15.00' | 90.01°

2.62' | 5.00' | 30.00'

2.64' 5.00' 30.21°

LEGEND

Line # | Length |

CONCRETE SIDEWALK PER CITY STD 1-19

DECOMPOSED GRANITE

2" GRIND & 2"-6" AC OVERLAY

FDAC

DETECTABLE DOMES PER CALTRANS STD PLAN A88A

POTHOLE

IMPROVEMENT PLANS FOR

CUPERTINO

No. 76008

DESIGN DESIGN CITY APPR. BY DATE APPR. DATE

BIKE BOULEVARD IMPROVEMENTS - PHASE 1 IMPROVEMENT PLAN - Merritt Drive at Vista Drive LOCATION 1

FOR CITY OF CUPERTINO USE PROJECT # <u>2017-01.05</u> PUBLIC WORKS INSPECTOR: VOICE MAIL: REVIEWED BY:

DATE



CITY OF **CUPERTINO C8**

SHEET 8 OF 37

MARCH 2019

Bellecci & Associates, inc. Designed:

Drawn:

File:

Checked:


Proj. Engr:


Civil Engineering • Land Surveying

7077 Koll Center Pkwy, Suite 210 Pleasanton, CA 94566

Phone (925) 681-4885


www.bellecci.com





CUPERTINO

CALIFORNIA



CONSTRUCTION NOTES

- CONSTRUCT NEW CONCRETE SIDEWALK AND BASE PER CITY STD. DETAIL 1-19. DOWEL INTO EXISTING PER CITY STD. DETAIL 1-23
- CONSTRUCT NEW CONCRETE CURB & GUTTER PER CITY STD. DETAIL
- 1-16 (A2-6); CURB HEIGHT VARIES SEE GRADING CONSTRUCT NEW SDMH OVER EXISTING STORM DRAIN PIPE PER CITY STD. DETAIL 3-12
- INTERLOCKING CONCRETE PAVERS SET ON CONCRETE BASE TO BE REPLACED (REUSE EXISTING PAVERS WITH CITY'S APPROVAL) - MATCH EXISTING
- PAVEMENT STRUCTURAL SECTION; REFER TO LANDSCAPE PLANS
- INSTALL TRUNCATED DOMES ON 4" THICK CONCRETE SUBSLAB OVER 4" THICK CLASS 2 AB COMPACTED TO 95% R.C.
- PROTECT IN PLACE EXISTING MONUMENT SIGN
- INSTALL 22 LF OF 12" PVC SDR-26; TRENCH BACKFILL PER CITY STD. DETAIL 4-24
- 8 INSTALL STANDARD DROP INLET CURB OPENING PER CITY STD. DETAIL 3-2

PROTECT IN PLACE EXISTING LANDSCAPING AND IRRIGATION SYSTEM

- 9 INSTALL DOUBLE SIDED W11-2/W16-7P ON NEW SIGN POST
- PROTECT IN PLACE EXISTING STAIRS
- \$\langle 12 \rangle SAWCUT LINE
- (13) 10" FULL-DEPTH ASPHALT CONCRETE (FDAC)
- PROTECT IN PLACE EXISTING SD BOX
- (15) NEW LANDSCAPING & IRRIGATION SEE LANDSCAPE PLANS
- PROTECT IN PLACE EXISTING FIRE HYDRANT AND APPURTENANT VALVES
- PRESERVE EXISTING INTERLOCKING CONCRETE PAVERS
- REPLACE COLORED CONCRETE BAND MATCH EXISTING; SEE LANDSCAPE PLANS

- PRESERVE EXISTING COLORED CONCRETE PAVING AND COLORED CONCRETE BAND
- (20) INSTALL 40 LF OF 12" PVC SDR-26; TRENCH BACKFILL PER CITY STD. DETAIL 4-24
- PROTECT IN PLACE EXISTING STREET LIGHT & CONCRETE FOUNDATION
- **₹22** REMOVE SIGN R1−6
- RELOCATE W11-2/W16-7P ON NEW SIGN POST, INSTALL NEW
- W11-2/W16-7P ON THE BACK SIDE 1 INSTALL R1-5L ON EXISTING STREETLIGHT POLE
- (25) INSTALL YIELD LINE PER CALTRANS STD. PLAN A24G
- 26 PAINT CURB RED
- PROTECT IN PLACE EXISTING CLEANOUT
- CONSTRUCT FLUSH CURB OVER 4" THICK CLASS 2 AB COMPACTED TO 95% R.C.
- (29) INSTALL 10' WIDE WHITE CONTINENTAL CROSSWALK PER CALTRANS STD. PLAN A24F
- REMOVE AND DISCARD EXISTING BOLLARD WITH LIGHT
- (31) RELOCATE EXISTING REGULAR BOLLARD
- (32) INSTALL NEW BOLLARD TO MATCH EXISTING REGULAR BOLLARD
- (33) PROTECT IN PLACE EXISTING BOLLARD WITH LIGHT
- PROTECT IN PLACE EXISTING CONCRETE SIDEWALK


CONCRETE SIDEWALK PER CITY STD 1-19 LANDSCAPE PLANTING & IRRIGATION, SEE LANDSCAPE & IRRIGATION PLANS CONCRETE BASE. MATCH EXISTING PAVEMENT

EXISTING INTERLOCKING CONCRETE PAVERS

POTHOLE

LEGEND

DETECTABLE DOMES PER CALTRANS STD PLAN A88A RESTORE INTERLOCKING CONCRETE PAVERS SET ON STRUCTURAL SECTION, SEE LANDSCAPE PLANS RESTORE COLORED CONCRETE BAND & BASE, SEE LANDSCAPE PLANS EXISTING COLORED CONCRETE BAND **FDAC**




HORIZONTAL CONTROL PLAN

SCALE: 1"=20'

Line Table						
Line #	Length	Direction				
L148	3.65'	N00° 39' 11"E°				
L150	6.90'	N35° 04' 49"W°				
L152	6.47'	N00° 45' 48"E°				
L154	5.97'	N40° 51' 58"E°				
L156	51.89'	N00° 51' 35"E°				
L158	6.94	N35° 01' 54"W°				
L160	6.47'	N00° 48′ 43″E°				
L162	5.97'	N40° 54' 53"E°				
L164	0.67	N00° 41' 38"E°				
L165	17.59'	N00° 56' 14"E°				
L167	16.88	N00° 42' 52"E°				

Curve #	Length	Radius	Delta
C162	28.69'	20.00'	82.19°
C163	28.66'	20.00'	82.12°
C161	3.51'	5.00'	40.22°
C160	2.80'	4.00'	40.10°
C159	3.13'	5.00'	35.84*
C158	3.14'	5.00'	35.95°
C157	3.50'	5.00'	40.07°
C156	2.80'	4.00'	40.10°
C155	3.13'	5.00'	35.84°
C154	3.12'	5.00'	35.73°



Bellecci & Associates, inc. Designed: Civil Engineering • Land Surveying

7077 Koll Center Pkwy, Suite 210 Pleasanton, CA 94566 Phone (925) 681-4885 www.bellecci.com

Checked: Proj. Engr: DESIGN DESIGN CITY APPR. BY DATE APPR. DATE **REVISIONS**

IMPROVEMENT PLANS FOR

BIKE BOULEVARD IMPROVEMENTS - PHASE 1 IMPROVEMENT PLAN - Torre Avenue at Town Center Lane LOCATION 3

CALIFORNIA CUPERTINO

FOR CITY OF CUPERTINO USE PROJECT # _2017-01.05_
PUBLIC WORKS INSPECTOR:
VOICE MAIL:
REVIEWED BY:




CITY OF **CUPERTINO**

C12

SHEET **12** OF **37**





GENERAL NOTE

CONSTRUCT SPEED TABLES PER CITY STD. DETAIL 1-17 (SEE SHEET C4). THE PLAN ONLY SHOWS APPROXIMATE LOCATIONS OF SPEED TABLES. CITY WILL STAKE IN FIELD FOR EXACT LOCATIONS.

	Date:	
Pallacei 9 Accesiates inc	Scale:	
放 Bellecci & Associates, inc.	Designed:	
Civil Engineering ● Land Surveying	Drawn:	

							2055
	Date:						OED PROFE
	Scale:						12/0
-	Designed:						F _C
	Drawn:						
	Checked:						 No. 7
	Proj. Engr:	DEVISIONS	DESIGN	DESIGN	CITY APPR.	APPR. DATE	STATE CI
	File:	REVISIONS	BY	DATE	APPR.	DATE	OF OF

IMPROVEMENT PLANS FOR

BIKE BOULEVARD IMPROVEMENTS - PHASE 1

SPEED TABLE PLAN

CUPERTINO

CALIFORNIA

FOR CITY OF CUPERTINO USE PROJECT # _2017-01.05
PUBLIC WORKS INSPECTOR:
VOICE MAIL:
REVIEWED BY:

,51.	195	

CITY OF CUPERTINO

C13

SHEET 13 OF 37

SHEET 13 OF 31

7077 Koll Center Pkwy, Suite 210 Pleasanton, CA 94566 Phone (925) 681-4885 www.bellecci.com



CUPERTINO

GENERAL NOTE

CONSTRUCT SPEED TABLES PER CITY STD. DETAIL 1-17 (SEE SHEET C4). THE PLAN ONLY SHOWS APPROXIMATE LOCATIONS OF SPEED TABLES. CITY WILL STAKE IN FIELD FOR EXACT LOCATIONS.

50	Q	25	50	100	200
			(IN 1"	FEET) '=50'	

	L
Rollogoi & Accopiatos inc	S
Bellecci & Associates, inc.	D
Civil Engineering ● Land Surveying	С

Civil Engineering • Land Surveying

7077 Koll Center Pkwy, Suite 210 Pleasanton, CA 94566
Phone (925) 681-4885
www.bellecci.com

Date: Scale: Designed: Drawn: Checked:						REG/Cz
						\
Proj. Engr:	REVISIONS	DESIGN BY	DESIGN DATE	CITY APPR.	APPR. DATE	

PROFESSIONAL REDDIVAL	
15/0 X	
A A A A A A A A A A A A A A A A A A A	
No. 76008	
STATE CIVIL ORNIT	

IMPROVEMENT PLANS FOR

BIKE BOULEVARD IMPROVEMENTS - PHASE 1

SPEED TABLE PLAN

CALIFORNIA

FOR CITY OF CUPERTINO USE PROJECT # <u>2017-01.05</u>	
PUBLIC WORKS INSPECTOR:	
VOICE MAIL:	
REVIEWED BY:	4,

-	
	45T.1955


CITY OF CUPERTINO

C14


SHEET **14** OF **37**

GENERAL SIGNING AND STRIPING NOTES:


- 1. ALL WORK SHALL CONFORM WITH THE LATEST CALIFORNIA MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (CA MUTCD), CALTRANS STANDARD PLANS AND SPECIFICATIONS, AND CITY OF CUPERTINO STANDARDS.
- 2. ALL EXISTING SIGNS AND POSTS SHALL REMAIN UNLESS OTHERWISE NOTED.
- 3. CONTRACTOR SHALL REMOVE ALL SIGNING AND STRIPING THAT CONFLICTS WITH THIS PLAN.
- 4. ALL UTILITIES AND IMPROVEMENTS THAT BECOME DAMAGED DURING CONSTRUCTION SHALL BE COMPLETELY RESTORED BY THE CONTRACTOR TO THE SATISFACTION OF THE CITY ENGINEER.
- 5. ALL LANE WIDTHS, WHEN ADJACENT TO THE CURB AND GUTTER, ARE MEASURED FROM THE FACE OF CURB.
- 6. LAYOUT AND CONTROL MARKS SHALL BE PLACED BY THE CONTRACTOR AND APPROVED BY THE CITY TRANSPORTATION ENGINEER PRIOR TO PLACEMENT OF ANY PERMANENT STRIPING, MARKERS, OR PAVEMENT MARKINGS. 48 HOURS NOTICE MUST BE GIVEN TO THE CITY FOR INSPECTION OF LAYOUT AND CONTROL MARKS.
- 7. ALL PERMANENT STRIPING AND PAVEMENT MARKINGS TO BE THERMOPLASTIC.
- 8. ALL EXISTING STRIPING THAT IS IN CONFLICT WITH THIS PLAN SHALL BE REMOVED.



<u>DETAIL 1</u> - BIKE LANE STRIPING AT CONFLICT POINTS



DETAIL 3 - GREEN PAVEMENT ENHANCEMENT THROUGH INTERSECTIONS/CONFLICT POINTS





WITH PERSON PAVEMENT MARKINGS (SEE CALTRANS STANDARD PLANS A24A & A24D)

SIGN WITH POST (NEW)

SIGN WITH POST (EXISTING)

SIGN WITH POST (REMOVE)


BLUE FIRE HYDRANT LOCATION PAVEMENT


m BIKE LOOP DETECTOR SYMBOL (SEE CALTRANS REVISED PLANS RSP A24C)

CALTRANS TYPE IV ARROW (SEE CALTRANS STANDARD PLANS A24A)

SHARED ROADWAY BICYCLE MARKING (SEE CALTRANS STANDARD PLAN A24C AND DETAIL 5 ON THIS SHEET)

GREEN PAVEMENT ENHANCEMENT





DETAIL 5 - SHARED ROADWAY BICYCLE MARKING PLACEMENT





Date:	3/8/19							~
Scale:	N/A							
Designed:	R. RODRIGUEZ							1 /
Drawn:	R. RODRIGUEZ							
Checked:	J. ELIA							
Proj. Engr	: J. ELIA	$\rfloor \wedge \vert$	REVISIONS	DESIGN	DESIGN	CITY	APPR.	
File:			VE AIRIONA	BY	DATE	APPR.	DATE	

PROFESSIONAL CENTRE OF CAUSON AND CIVIL

IMPROVEMENT PLANS FOR

CUPERTINO

BIKE BOULEVARD IMPROVEMENTS - PHASE 1 SIGNING AND STRIPING

SIGNING AND STRIPING NOTES, LEGEND, AND DETAILS


CALIFORNIA


FOR CITY OF CUPERTINO USE PROJECT # __2017-01.05 __ PUBLIC WORKS INSPECTOR: VOICE MAIL: REVIEWED BY:



CITY OF CUPERTINO

SHEET 15 OF 37





www.hextrans.com

HEXAGON TRANSPORTATION

CONSULTANTS, INC.

4 North Second Street, Suite 400

San Jose, California 95113

Ph: (408) 971-6100

PROFESSIONAL PROFE

IMPROVEMENT PLANS FOR

1 INCH = 20 FEET

GRAPHIC SCALE

BIKE BOULEVARD IMPROVEMENTS - PHASE 1

SIGNING AND STRIPING IMPROVEMENTS
N. PORTAL AVE. FROM STEVENS CREEK BLVD. TO
AMHERST DR. (LOCATION 1)

CUPERTINO

CALIFORNIA

REVIEWED BY:

ST. 1955


CITY OF CUPERTINO

SS-2

SHEET 16 OF **37**

3 INSTALL BLUE PAVEMENT MARKER, IN LINE WITH THE FIRE HYDRANT AND 6" SOUTH OF THE CENTER DETAIL 22 LINE.

4 INSTALL BLUE PAVEMENT MARKER, IN LINE WITH THE FIRE HYDRANT AND 6" EAST OF THE CENTERLINE.





[•] SEE SHEET SS-1 FOR GENERAL SIGNING AND STRIPING NOTES AND LEGEND.

HEXAGON TRANSPORTATION CONSULTANTS, INC. 4 North Second Street, Suite 400 San Jose, California 95113

]	0
ORTATION	Date:	3/8/19						J	- :
JKIATIOH	Scale:	1" = 20'						١,	[[ž
	Designed:	R. RODRIGUEZ						l //	REGISTE
•	Drawn:	R. RODRIGUEZ							(*) *
www.hextrans.com	Checked:	J. ELIA						1 8	1
	Proj. Engr	: J. ELIA	REVISIONS	DESIGN	DESIGN DATE	CITY APPR.	APPR. DATE		\
	File:		REVISIONS	BY	DATE	APPR.	DAIL		

IMPROVEMENT PLANS FOR

BIKE BOULEVARD IMPROVEMENTS - PHASE 1 SIGNING AND STRIPING IMPROVEMENTS

CUPERTINO

N. PORTAL AVE. AND AMHERST DR. (LOCATION 1)

CALIFORNIA

FOR CITY OF CUPERTINO USE PROJECT # 2017-01.05
PUBLIC WORKS INSPECTOR:
VOICE MAIL:
REVIEWED BY:
NAME

GRAPHIC SCALE

1 INCH = 20 FEET

CITY OF CUPERTINO

MARCH 2019

Ph: (408) 971-6100


CONTRACTOR AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY; THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY AND HOLD THE OWNER AND THE ENGINEER HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WOR THIS PROJECT, EXCEPTING FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR THE ENGINEER.

~CA: 1−800−227−2600 -

CALL TWO WORKING DAYS BEFORE YOU DIG

SS-3

SHEET 17 OF **37**



CA: 1-800-227-2600-CALL TWO WORKING DAYS BEFORE YOU DIG

THIS PLAN IS ACCURATE FOR SIGNING AND STRIPING WORK ONLY.EXISTING SIGNING AND STRIPING NOT FULLY DOCUMENTS ON THIS PLAN.

• SEE SHEET SS-1 FOR GENERAL SIGNING AND STRIPING NOTES AND LEGEND.

HEXAGON TRANSPORTATION CONSULTANTS, INC. 4 North Second Street, Suite 400 San Jose, California 95113

ORTATION	Date:	3/8/19						
UKTATIUH	Scale:	1" = 20'] ,
(Designed:	R. RODRIGUEZ] //
	Drawn:	R. RODRIGUEZ]
	Checked:	J. ELIA						<u></u> '
 	Proj. Engr:	J. ELIA	REVISIONS	DESIGN	DESIGN DATE	CITY	APPR.	
	File:		IVE AIGIOIAG	BA	DAIL	APPR.	DATE	

IMPROVEMENT PLANS FOR **BIKE BOULEVARD IMPROVEMENTS - PHASE 1**

CUPERTINO

SIGNING AND STRIPING IMPROVEMENTS N. PORTAL AVE. FROM AMHERST DR. TO MERRITT DR. (LOCATION 1)

CALIFORNIA

FOR CITY OF CUPERTINO USE PUBLIC WORKS INSPECTOR: VOICE MAIL: REVIEWED BY:

GRAPHIC SCALE


1 INCH = 20 FEET

CITY OF CUPERTINO SS-4

SHEET 18 OF **37**

Ph: (408) 971-6100

CONTRACTOR AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY AND HOLD THE OWNER AND THE ENGINEER HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT, EXCEPTING FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR THE ENGINEER.







THIS PLAN IS ACCURATE FOR SIGNING AND STRIPING WORK ONLY.EXISTING SIGNING AND STRIPING NOT FULLY DOCUMENTS ON THIS PLAN. • SEE SHEET SS-1 FOR GENERAL SIGNING AND STRIPING NOTES AND LEGEND.

GRAPHIC SCALE

1 INCH = 20 FEET

HEXAGON TRANSPORTATION CONSULTANTS, INC. 4 North Second Street, Suite 400 San Jose, California 95113

								1
ORTATION	Date:	3/8/19						\
JKIATIOH	Scale:	1" = 20'						
	Designed:	R. RODRIGUEZ						
•	Drawn:	R. RODRIGUEZ						
	Checked:	J. ELIA						
 	Proj. Engr:	: J. ELIA	DEVICIONS	DESIGN	DESIGN DATE	CITY	APPR.	
	File:		REVISIONS	BY	DATE	APPR.	DATE	

IMPROVEMENT PLANS FOR

BIKE BOULEVARD IMPROVEMENTS - PHASE 1

SIGNING AND STRIPING IMPROVEMENTS MERRITT DR. FROM PORTAL AVE. TO N. BLANEY AVE. (LOCATION 1)

CALIFORNIA

FOR CITY OF CUPERTINO USE PROJECT # _2017-01.05 PUBLIC WORKS INSPECTOR: VOICE MAIL: REVIEWED BY:


CITY OF CUPERTINO SS-5

SHEET 19 OF **37**

MARCH 2019

Ph: (408) 971-6100

CUPERTINO





CA: 1−800−227−2600 **−**

THIS PLAN IS ACCURATE FOR SIGNING AND STRIPING WORK ONLY.EXISTING SIGNING AND STRIPING NOT FULLY DOCUMENTS ON THIS PLAN.

• SEE SHEET SS-1 FOR GENERAL SIGNING AND STRIPING NOTES AND LEGEND.

HEXAGON TRANSPORTATION CONSULTANTS, INC. 4 North Second Street, Suite 400 San Jose, California 95113

ORTATION	Date:	3/8/19						
JKIMITUIT	Scale:	1" = 20'						<u> </u>
	Designed:	R. RODRIGUEZ						
	Drawn:	R. RODRIGUEZ						
	Checked:	J. ELIA						'
www.hextrans.com	Proj. Engr:	: J. ELIA	REVISIONS	DESIGN	DESIGN DATE	CITY	APPR.	
-	File:		KE VISIONS	BA	DATE	APPR.	DAIL	

IMPROVEMENT PLANS FOR

BIKE BOULEVARD IMPROVEMENTS - PHASE 1

CUPERTINO


SIGNING AND STRIPING IMPROVEMENTS MERRITT DR. FROM N. BLANEY AVE. TO RANDY LN. (LOCATION 1)

CALIFORNIA

FOR CITY OF CUPERTINO USE PROJECT # 2017-01.05 PUBLIC WORKS INSPECTOR: VOICE MAIL: REVIEWED BY:

GRAPHIC SCALE


1 INCH = 20 FEET



CITY OF CUPERTINO SS-6

SHEET 20 OF **37**

Ph: (408) 971-6100





CA: 1-800-227-2600 -

THIS PLAN IS ACCURATE FOR SIGNING AND STRIPING WORK ONLY.
EXISTING SIGNING AND STRIPING NOT FULLY DOCUMENTS ON THIS PLAN.
SEE SHEET SS-1 FOR GENERAL SIGNING AND STRIPING NOTES AND LEGEND.

HEXAGON TRANSPORTATION

CONSULTANTS, INC.

4 North Second Street, Suite 400
San Jose, California 95113

Ph: (408) 971-6100

ORTATION	Date:	3/8/19] 🗸
KIATIOH	Scale:	1" = 20'						
	Designed:	R. RODRIGUEZ						
	Drawn:	R. RODRIGUEZ] '4
	Checked:	J. ELIA] \(\)
www.hextrans.com	Proj. Engr	: J. ELIA	REVISIONS	DESIGN	DESIGN DATE	CITY APPR.	APPR.	
	File:		NE VISIONS	BA	DATE	APPR.	DAIL	

IMPROVEMENT PLANS FOR

CUPERTINO

BIKE BOULEVARD IMPROVEMENTS - PHASE 1 SIGNING AND STRIPING IMPROVEMENTS

SIGNING AND STRIPING IMPROVEMENTS MERRITT DR. FROM VISTA DR. TO LARRY WAY (LOCATION 1)

CALIFORNIA

PROJECT #	2017-01.0	_
PUBLIC WORKS INSPECTOR:		
VOICE MAIL:		
REVIEWED BY:		
	PROJECT # _ PUBLIC WORKS INSPECTOR: VOICE MAIL:	PUBLIC WORKS INSPECTOR: VOICE MAIL:

GRAPHIC SCALE

1 INCH = 20 FEET




CITY OF CUPERTINO

SS-7

SHEET 21 OF **37**

1 INSTALL LIMIT LINE 4' FROM CROSSWALK.





• THIS PLAN IS ACCURATE FOR SIGNING AND STRIPING WORK ONLY. • EXISTING SIGNING AND STRIPING NOT FULLY DOCUMENTS ON THIS PLAN. • SEE SHEET SS-1 FOR GENERAL SIGNING AND STRIPING NOTES AND LEGEND.

HEXAGON TRANSPORTATION CONSULTANTS, INC.

4 North Second Street, Suite 400 San Jose, California 95113 Ph: (408) 971-6100 www.hextrans.com

Cnecked: Proj. Engr:			REVISIONS	DESIGN BY	DESIGN DATE	CITY APPR.	APPR.	\
Checkea:	J. ELIA							//
01 1 1								<i>\\</i>
Drawn:	R. RODRIGUEZ							
Designed:	R. RODRIGUEZ							REGIS
Scale:	1" = 20'							
Date:	3/8/19							
	Scale: Designed: Drawn:	Scale: 1" = 20' Designed: R. RODRIGUEZ Drawn: R. RODRIGUEZ	Scale: 1" = 20' Designed: R. RODRIGUEZ Drawn: R. RODRIGUEZ	Scale: 1" = 20' Designed: R. RODRIGUEZ Drawn: R. RODRIGUEZ	Scale: 1" = 20' Designed: R. RODRIGUEZ Drawn: R. RODRIGUEZ	Scale: 1" = 20' Designed: R. RODRIGUEZ Drawn: R. RODRIGUEZ	Scale: 1" = 20' Designed: R. RODRIGUEZ Drawn: R. RODRIGUEZ	Scale: 1" = 20' Designed: R. RODRIGUEZ

IMPROVEMENT PLANS FOR

CUPERTINO

BIKE BOULEVARD IMPROVEMENTS - PHASE 1 SIGNING AND STRIPING IMPROVEMENTS

BANDLEY DR. AND MARIANI AVE. (LOCATION 5)

CALIFORNIA

FOR CITY OF CUP PROJECT # _20	PERTINO USE 17-01.05
PUBLIC WORKS INSPECTOR:	
VOICE MAIL:	
REVIEWED BY:	
NAME	DATE

GRAPHIC SCALE

1 INCH = 20 FEET

CITY OF CUPERTINO SS-8

SHEET 22 OF **37**

CONTRACTOR AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY AND HOLD THE OWNER AND THE ENGINEER HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORI

BEARDON DRIVE MINSTALL 12' WIDE WHITE CONTINENTAL CROSSWALK, REFER TO CALTRANS STANDARD PLAN A24F EXISTING W14-2 SIGN AND -POST TO REMAIN INSTALL W11-2-SIGN, W16-7P SIGN, AND POST INSTALL SHARED ROADWAY
BICYCLE MARKING (TYP., 3
LOCATIONS, THIS SHEET)
(SEE DETAIL 5, SHEET SS-1) GRAPHIC SCALE 1 INCH = 20 FEET

DESIGN DESIGN CITY APPR. BY DATE APPR. DATE

REVISIONS





IMPROVEMENT PLANS FOR

CALIFORNIA

BIKE BOULEVARD IMPROVEMENTS - PHASE 1


CUPERTINO

MATCH LINE J-J, SEE SHEET E-10

SIGNING AND STRIPING IMPROVEMENTS BEARDON DR. AND GREENLEAF DR. (LOCATION 5)

PROJECT # <u>2017-01.05</u> PUBLIC WORKS INSPECTOR: VOICE MAIL: REVIEWED BY:

FOR CITY OF CUPERTINO USE



CITY OF CUPERTINO

SS-9 SHEET 23 OF **37**

• THIS PLAN IS ACCURATE FOR SIGNING AND STRIPING WORK ONLY.

HEXAGON TRANSPORTATION

CONSULTANTS, INC.

4 North Second Street, Suite 400 San Jose, California 95113

Ph: (408) 971-6100

• EXISTING SIGNING AND STRIPING NOT FULLY DOCUMENTS ON THIS PLAN. • SEE SHEET SS-1 FOR GENERAL SIGNING AND STRIPING NOTES AND LEGEND.

www.hextrans.com

Date: 3/8/19

Checked: J. ELIA

Proj. Engr: J. ELIA

Scale: 1" = 20'

Designed: R. RODRIGUEZ

Drawn: R. RODRIGUEZ

20833 GREENLEAF DRIVE 20777 GREENLEAF DRIVE INSTALL SHARED ROADWAY
BICYCLE MARKING (TYP. 7
LOCATIONS, THIS SHEET)
(SEE DETAIL 5, SHEET SS-1) **(12**) GREENLEAF DRIVE





THIS PLAN IS ACCURATE FOR SIGNING AND STRIPING WORK ONLY.
EXISTING SIGNING AND STRIPING NOT FULLY DOCUMENTS ON THIS PLAN.
SEE SHEET SS-1 FOR GENERAL SIGNING AND STRIPING NOTES AND LEGEND.

HEXAGON TRANSPORTATION CONSULTANTS, INC. 4 North Second Street, Suite 400 San Jose, California 95113

www.hextrans.com	Proj. Engr: J. ELI <i>i</i>	А	$\overline{\wedge}$	REVISIONS	DESIGN	DESIGN DATE	CITY	APPR. DATE	
	Checked: J. ELIA	А							
•	Drawn: R. ROI	DRIGUEZ							
	Designed: R. ROI	DRIGUEZ							
JKIATIOH	Scale: 1" = :	20'							
DRTATION	Date: 3/8/1	19							_

IMPROVEMENT PLANS FOR

BIKE BOULEVARD IMPROVEMENTS - PHASE 1

SIGNING AND STRIPING IMPROVEMENTS GREENLEAF DR. FROM BEARDON DR. TO GLENCOE DR. (LOCATION 5)

FOR CITY OF CUPERTINO USE PROJECT # 2017-01.05 PUBLIC WORKS INSPECTOR: VOICE MAIL: REVIEWED BY:



CITY OF CUPERTINO SS-10

MARCH 2019

Ph: (408) 971-6100

CUPERTINO

CALIFORNIA

SHEET 24 OF **37**



CA: 1-800-227-2600 -CALL TWO WORKING DAYS BEFORE YOU DIG

GRAPHIC SCALE

1 INCH = 20 FEET



CUPERTINO

- THIS PLAN IS ACCURATE FOR SIGNING AND STRIPING WORK ONLY.EXISTING SIGNING AND STRIPING NOT FULLY DOCUMENTS ON THIS PLAN.
- SEE SHEET SS-1 FOR GENERAL SIGNING AND STRIPING NOTES AND LEGEND.

HEXAGON TRANSPORTATION CONSULTANTS, INC.

4 North Second Street, Suite 400 San Jose, California 95113 Ph: (408) 971-6100 www.hextrans.com

Date: 3/8/19 Scale: 1" = 20' Designed: R. RODRIGUEZ Drawn: R. RODRIGUEZ Checked: J. ELIA Proj. Engr: J. ELIA REVISIONS

IMPROVEMENT PLANS FOR

BIKE BOULEVARD IMPROVEMENTS - PHASE 1

SIGNING AND STRIPING IMPROVEMENTS GREENLEAF DR. FROM GLENCOE DR. TO FLORA VISTA AVE. (LOCATION 5)

CALIFORNIA


FOR CITY OF CUPERTINO USE PROJECT # _2017-01.05 PUBLIC WORKS INSPECTOR: VOICE MAIL:

CITY OF CUPERTINO SS-11

SHEET 25 OF **37**







CALIFORNIA

- THIS PLAN IS ACCURATE FOR SIGNING AND STRIPING WORK ONLY.
 EXISTING SIGNING AND STRIPING NOT FULLY DOCUMENTS ON THIS PLAN.
 SEE SHEET SS-1 FOR GENERAL SIGNING AND STRIPING NOTES AND LEGEND.

HEXAGON TRANSPORTATION CONSULTANTS, INC.

North Second Street, Suite 400		t
n Jose, California 95113		L
n: (408) 971-6100	www.hextrans.com	Γ
		L

	Date:	3/8/19]	7
	Scale:	1" = 20'							/	
	Designed:	R. RODRIGUEZ							[[REGISTE
	Drawn:	R. RODRIGUEZ								الشا
	Checked:	J. ELIA								1/
m	Proj. Engr:	: J. ELIA	\land	REVISIONS	DESIGN	DESIGN	CITY APPR.	APPR. DATE		/
	File:			REVISIONS	BY	DATE	APPR.	DAIL		

IMPROVEMENT PLANS FOR

CUPERTINO

BIKE BOULEVARD IMPROVEMENTS - PHASE 1

SIGNING AND STRIPING IMPROVEMENTS GREENLEAF DR. FROM FLORA VISTA AVE. TO ANN ARBOR AVE. (LOCATION 5)


	PUBLIC WORKS INSPECTOR:	
PR	VOICE MAIL:	
	REVIEWED BY:	
	NAME	DA


FOR CITY OF CUPERTINO USE PROJECT # __2017-01.05__



CITY OF CUPERTINO SS-12

SHEET 26 OF **37**





CA: 1−800−227−2600 CALL TWO WORKING DAYS BEFORE YOU DIG

THIS PLAN IS ACCURATE FOR SIGNING AND STRIPING WORK ONLY.EXISTING SIGNING AND STRIPING NOT FULLY DOCUMENTS ON THIS PLAN. • SEE SHEET SS-1 FOR GENERAL SIGNING AND STRIPING NOTES AND LEGEND.

HEXAGON TRANSPORTATION CONSULTANTS, INC. 4 North Second Street, Suite 400 San Jose, California 95113

									1
ORTATION	Date:	3/8/19							`
OKIAIIOII	Scale:	1" = 20'							
(Designed:	R. RODRIGUEZ							
	Drawn:	R. RODRIGUEZ							
	Checked:	J. ELIA							
www.hextrans.com	Proj. Engr:	: J. ELIA	_	REVISIONS	DESIGN	DESIGN	CITY	APPR. DATE	
	File:			RE VISIONS	BY	DATE	APPR.	DAIE	
	•			_				•	

IMPROVEMENT PLANS FOR

BIKE BOULEVARD IMPROVEMENTS - PHASE 1

SIGNING AND STRIPING IMPROVEMENTS GREENLEAF DR. FROM ANN ARBOR AVE. TO CASTINE AVE. (LOCATION 5)

CUPERTINO CALIFORNIA FOR CITY OF CUPERTINO USE PROJECT # __2017-01.05__ PUBLIC WORKS INSPECTOR: VOICE MAIL:

CITY OF CUPERTINO SS-13

SHEET 27 OF **37**

MARCH 2019

Ph: (408) 971-6100

STRUCTURAL SPECIFICATIONS

CONCRETE

ALL CONCRETE SHALL HAVE PROPERTIES AS LISTED BELOW.

CONCRETE	MIN. 28 DAY	MAX. SIZE	MAX. SLUMP	W/C F	RATIO
ELEMENT	COMPRESSIVE STRENGTH	AGGREGATE (INCHES)	(INCHES)	W/O FLYASH	W/25% FLYAS
PIERS & WALL	3000	3/4	4	.55	.50

SHOTCRETE

SHOTCRETE SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE AMERICAN CONCRETE INSTITUTE STANDARD 506.2-13, "RECOMMENDED PRACTICE FOR SHOTCRETING". SHOTCRETE SHALL HAVE A MINIMUM 28 DAY COMPRESSIVE STRENGTH OF 3000 PSI AND A MINIMUM SLUMP OF 2" AS DETERMINED BY TESTING THE SHOTCRETE DURING CONSTRUCTION. THE CONTRACTOR SHALL HIRE A PROFESSIONAL TESTING LABORATORY TO DETERMINE THE MIX PROPORTIONS, CONSTRUCTION PROCEDURES AND TESTING METHODS FOR SHOTCRETING. SHOTCRETING SHALL BE MOISTURE CURED UNLESS OTHERWISE APPROVED BY THE ENGINEER.

REINFORCING STEEL

BARS FOR REINFORCING SHALL BE GRADE 60 DEFORMED BARS CONFORMING TO ASTM A-615 INCLUDING SUPPLEMENT S1. LAP SPLICES SHALL BE IN ACCORDANCE WITH ACI 318 UNLESS NOTED OTHERWISE ON THE PLANS.

SHOP DRAWINGS. FOR THE ENGINEERS REVIEW WILL BE REQUIRED AS FOLLOWS:

MIX DESIGNS; REINFORCING STEEL;

CONTRACTOR SHALL SUBMIT TWO SETS OF PRINTS AND ONE SET OF SEPIAS FOR REVIEW. FABRICATION SHALL NOT PROCEED UNTIL SHOP DRAWINGS HAVE BEEN REVIEWED BY THE ENGINEER.

CONSTRUCTION LIABILITY

CONSTRUCTION CONTRACTOR AND HIS SUBCONTRACTORS AGREE THAT IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES, CONSTRUCTION CONTRACTOR AND HIS SUBCONTRACTORS WILL BE REQUIRED TO ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THE PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY; THAT THIS REQUIREMENT SHALL BE MADE TO APPLY CONTINUOUSLY AND NOT LIMITED TO NORMAL WORKING HOURS, AND CONSTRUCTION CONTRACTOR AND HIS SUBCONTRACTORS FURTHER AGREE TO DEFEND, INDEMNIFY AND HOLD DESIGN PROFESSIONAL HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT, EXCEPT LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF DESIGN PROFESSIONAL.

EXISTING CONDITIONS

THE CONTRACTOR OR SUBCONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS PRIOR TO BEGINNING CONSTRUCTION AND OR ORDERING MATERIAL, ANY DISCREPANCIES DISCOVERED SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER IMMEDIATELY.

REVISIONS

SPECIAL INSPECTIONS

THE OWNER SHALL EMPLOY A SPECIAL INSPECTOR DURING CONSTRUCTION ON THE FOLLOWING TYPES OF WORK:

CONCRETE

- DURING THE TAKING OF TEST SPECIMENS AND PLACING OF ALL REINFORCED CONCRETE AND PNEUMATICALLY

REINFORCING STEEL

- PERIODICALLY, DURING THE PLACING OF REINFORCING STEEL FOR ALL CONCRETE REQUIRED TO HAVE SPECIAL

SPECIAL INSPECTOR

- THE SPECIAL INSPECTOR SHALL BE A QUALIFIED PERSON WHO SHALL DEMONSTRATE HIS COMPETENCE, TO THE SATISFACTION OF THE BUILDING OFFICIAL, FOR INSPECTION OF A PARTICULAR TYPE OF CONSTRUCTION OR OPERATION REQUIRING SPECIAL INSPECTION.

DUTIES AND RESPONSIBILITIES OF THE SPECIAL INSPECTOR


- THE SPECIAL INSPECTOR SHALL OBSERVE THE WORK ASSIGNED FOR CONFORMANCE WITH THE APPLICABLE DESIGN DRAWINGS AND SPECIFICATIONS.
- THE SPECIAL INSPECTOR SHALL FURNISH INSPECTION REPORTS TO THE BUILDING OFFICIAL, THE ENGINEER OR ARCHITECT OF RECORD, AND OTHER DESIGNATED PERSONS. ALL DISCREPANCIES SHALL BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE CONTRACTOR FOR CORRECTION, THEN, IF UNCORRECTED, THE PROPER DESIGN AUTHORITY AND TO THE BUILDING OFFICIAL.
- THE SPECIAL INSPECTOR SHALL SUBMIT A FINAL SIGNED REPORT STATING WHETHER THE WORK REQUIRING SPECIAL INSPECTION WAS, TO THE BEST OF HIS KNOWLEDGE, IN CONFORMANCE WITH THE APPROVED PLANS AND SPECIFICATIONS AND THE APPLICABLE WORKMANSHIP PROVISION OF THIS CODE.

— #4 @ 18" O.C. AT € OF WALL


LAP 2'-0" AT ALL SPLICES

SCALE: 3/4" = 1'-0"

CUPERTINO



PRELIMINARY PROPERTY LINES





6" CAST-IN-PLACE CONCRETE OR SHOTCRETE WALL

(3)-#4 AT C OF WALL AND PIER

(6)-#5 VERTICAL-

(3)-#4 FROM WALL

16" DRILLED PIER

SECTION

#3 SPIRAL BAR w/ 3" PITCH

IMPROVEMENT PLANS FOR

BIKE BOULEVARD IMPROVEMENTS - PHASE 1 STRUCTURAL PLAN AND DETAILS - Greenleaf Drive at **Bandley Drive and Mariani Avenue**

FOR CITY OF CUPERTINO USE PROJECT # <u>2017-01.05</u> PUBLIC WORKS INSPECTOR: VOICE MAIL: REVIEWED BY:



CITY OF **CUPERTINO**

S1 SHEET **28** OF **37**

MARCH 2019

1340 STEVENS CREEK BLVD. #200

Proj. Engr:

LAYOUT NOTES

- I. CONTRACTOR SHALL VERIFY ALL UTILITIES, GRADES, EXISTING CONDITIONS AND DIMENSIONS IN THE FIELD PRIOR TO COMMENCING WORK. ALL DISCREPANCIES OR QUESTIONS SHALL BE BROUGHT TO THE ATTENTION OF THE LANDSCAPE ARCHITECT FOR RESOLUTION.
- 2. ALL WRITTEN DIMENSIONS SUPERCEDE ALL SCALED DISTANCES AND DIMENSIONS. DIMENSIONS SHOWN ARE FROM THE FACE OF THE BUILDING, WALL, BACK OF CURB, EDGE OF WALK, PROPERTY LINE, OR CENTERLINE OF COLUMN UNLESS OTHERWISE NOTED ON THE DRAWINGS.
- 3. ALL DIMENSIONS AT ROADWAY ARE TO FACE OF CURB.
- 4. ALL ANGLES ARE 45 DEGREE, 90 DEGREE, OR 135 DEGREE UNLESS OTHERWISE NOTED.
- 5. ALL CURVES AND ALL TRANSITIONS BETWEEN CURVES AND STRAIGHT EDGES SHALL BE SMOOTH.
- 6. ALL RETURN RADII AND CURB DATA ARE TO FACE OF CURB.
- 7. SCORE LINES IN SIDEWALKS SHALL BE SPACED TO EQUAL THE WIDTH OF THE WALKWAY, UNLESS OTHERWISE SHOWN. EXPANSION JOINTS IN SIDEWALKS SHALL BE 20' ON CENTER MAXIMUM.
- 8. SIDEWALK, CURB AND GUTTER, GRADING AND DRAINAGE IS BASED ON DRAWINGS PREPARED BY THE
- 9. STATIONING HEREON IS ALONG CONSTRUCTION CENTERLINE UNLESS OTHERWISE SHOWN OR
- 10. ANY EXTRA CONSTRUCTION STAKING NECESSITATED SOLELY BY THE CONTRACTOR'S NEGLIGENCE WILL BE CHARGED TO THE CONTRACTOR ON A TIME AND EXPENSES BASIS AND PAID FOR BY THE CONTRACTOR.
- 11. SEE IRRIGATION DRAWINGS FOR GENERAL SYSTEM REQUIREMENTS AND FOR LOCATION OF IRRIGATION MAINLINE PIPING. SLEEVES TO ACCOMMODATE IRRIGATION PIPING, SIZED AS NEEDED, SHALL BE IN PLACE UNDER AND THROUGH SLABS AND WALLS, PRIOR TO POURING.
- 12. ALL CONCRETE PAVEMENTS SHALL BE DOWELED INTO CURBS, SIDEWALKS, AND BUILDING FOUNDATIONS.
- 13. ALL TYPICAL DETAILS SHALL APPLY UNLESS NOTED OTHERWISE.
- 14. ANY AND ALL WORK WITHIN CITY RIGHT OF WAY SHALL CONFORM TO ALL CITY STANDARD DETAILS AND SPECIFICATIONS.
- 15. ALL EXISTING ITEMS TO REMAIN SHALL BE PROTECTED AS REQUIRED. ANY DAMAGED ITEMS SHALL BE FULLY REPAIRED OR REPLACED AT THE CONTRACTOR'S EXPENSE TO THE FULL SATISFACTION OF THE OWNER.
- 16. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY COORDINATION WITH SUBCONTRACTORS AS REQUIRED TO ACCOMPLISH OPERATIONS.
- 17. ALL QUANTITIES AND PAY ITEMS ARE AND WILL BE BASED ON HORIZONTAL MEASUREMENTS.
- 18. ALL PATTERNS, LINE TYPES, AND SYMBOLS SHOWN WITHIN THE PLAN SET REFERENCE THE LAYOUT LEGEND AND ARE PART OF THE SCOPE OF WORK. CALLOUTS ARE SHOWN FOR CLARIFICATION OF WORK, BUT DO NOT INDICATE EVERY AND ALL INSTANCES OF SUCH WORK. THE CONTRACTOR SHALL REQUEST CLARIFICATION TO ANY ITEMS (INCLUDING BUT NOT LIMITED TO PAVING, WALLS, FINISHES, COLORS, FENCING, FOUNTAINS, POTS, AND SITE FURNITURE) NOT CLEARLY IDENTIFIED TO BE PART OF THE SCOPE OF WORK PRIOR TO BID.
- 19. THE CONTRACT DRAWINGS MUST BE ACCOMPANIED BY CONTRACT SPECIFICATIONS. THE CONTRACTOR MUST CONTACT THE LANDSCAPE ARCHITECT AT 925-736-8176 FOR SPECIFICATIONS IF NOT RECEIVED.

PLANTING NOTES

SENERAL

ALL WORK SHALL BE PERFORMED BY PERSONS FAMILIAR WITH PLANTING WORK AND UNDER THE SUPERVISION OF A QUALIFIED PLANTING FOREMAN.

- ALL QUANTITIES AND PLANT COUNTS ARE FOR THE CONVENIENCE OF THE CONTRACTOR. IN CASE OF DISCREPANCIES, THE PLAN SHALL GOVERN.
- 3. THE LANDSCAPE ARCHITECT RESERVES THE RIGHT TO MAKE SUBSTITUTIONS, ADDITIONS, AND DELETIONS IN THE PLANTING SCHEME AS THEY FEEL NECESSARY WHILE WORK IS IN PROGRESS, UPON APPROVAL BY THE OWNER. SUCH CHANGES ARE TO BE ACCOMPANIED BY EQUITABLE ADJUSTMENTS IN THE CONTRACT PRICE, WHEN NECESSARY.
- 4. PLANT MATERIAL LOCATIONS SHOWN ARE DIAGRAMMATIC AND MAY BE SUBJECT TO CHANGE IN THE FIELD BY THE LANDSCAPE ARCHITECT. PLANT LOCATIONS ARE TO BE ADJUSTED IN THE FIELD AS NECESSARY TO SCREEN UTILITIES, BUT SHALL NOT BLOCK WINDOWS, BLOCK SIGNS NOR IMPEDE ACCESS.
- 5. THE DESIGN INTENT OF THE PLANTING PLAN IS TO ESTABLISH AN ATTRACTIVE MATURE LANDSCAPE APPEARANCE. FUTURE PLANT GROWTH WILL NECESSITATE TRIMMING, SHAPING, AND IN SOME CASE REMOVAL OF TREES AND SHRUBS AS AN ON-GOING MAINTENANCE PROCEDURE.
- 6. ALL PLANTING AREA MUST BE IRRIGATED WITH AUTOMATIC IRRIGATION SYSTEM. IRRIGATION SYSTEM SHALL BE FULLY AUTOMATED AND OPERATIONAL WITH FULL COVERAGE PRIOR TO PLANTING.
- 7. CONTRACTOR TO REVIEW ALL EXISTING, PROPOSED, & AS BUILT UTILITY PLANS PRIOR TO CONSTRUCTION. CONTRACTOR TO TAKE PRECAUTIONS IN EXCAVATION OF ALL TREE PLANTING PITS. CONTRACTOR TO NOTIFY LANDSCAPE ARCHITECT OF ANY CONFLICTS FOUND DURING CONSTRUCTION.
- 8. CONTRACTOR TO PROVIDE AND ARRANGE FOR PLANT MATERIAL THRU CONTRACT GROW, PLANT BROKERS, OR DIRECT PURCHASE AS REQUIRED FOR THE FULL IMPLEMENTATION OF THE PROJECTS PLANTING PLAN. CONTRACTOR MUST SUBMIT WITHIN 30 DAYS AFTER AWARD OF A BID A DETAILED NURSERY LIST OF SECURED PLANT MATERIAL, CONTRACT GROW PLANT MATERIAL, AND ANY SUBSTITUTION REQUESTS. CONTRACTOR SHALL ARRANGE AND SECURE ALL PLANT MATERIAL WITHIN 30 DAYS OF BID. UPON DELIVERY, PLANT MATERIAL THAT DOES NOT MEET NURSERY STANDARDS, IS ROOTBOUND, OF POOR QUALITY & HEALTH, SUBSTANDARD SIZE, AND / OR IS NOT APPROVED BY THE LANDSCAPE ARCHITECT SHALL BE REPLACED AT THE CONTRACTOR'S EXPENSE. MATERIAL WHICH IS NOT SECURED AND IS UNAVAILABLE IN THE SIZE SPECIFIED SHALL BE UP-SIZED, IF AVAILABLE. ALL REPLACEMENT MATERIAL, SUBSTITUTIONS OR UP-SIZED PLANT MATERIAL MUST BE PROVIDED AS REQUIRED FOR THE FULL IMPLEMENTATION OF THE PLANTING PLAN AT NO ADDITIONAL COST TO THE CONTRACT AND OWNER.
- 9. PROCUREMENT OF PLANT MATERIAL SHALL NOT BE LIMITED TO NORTHERN CALIFORNIA. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL TRUCKING, INSPECTIONS, AND INCIDENTALS FOR PROVIDING PLANT MATERIAL FROM SOURCES OUT OF STATE AS REQUIRED BY THE PROJECT PLANTING PLAN.

EXISTING PLANT MATERIAL

- I. ALL EXISTING PLANT MATERIAL, TREES, OR LAWN TO REMAIN MUST BE PROTECTED AND MAINTAINED IN PLACE BY THE CONTRACTOR.
- 2. ANY DAMAGED MATERIAL MUST BE FULLY REPLACED TO MATCH EXISTING BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT AND OWNER.
- CONTRACTOR MUST MAINTAIN ANY EXISTING IRRIGATION SYSTEMS OR PROVIDE TEMPORARY IRRIGATION SYSTEMS AS REQUIRED TO ALL EXISTING PLANTING AREAS TO REMAIN.

SOILS

THE CONTRACTOR MUST PROVIDE AN AGRICULTURAL SUITABILITIES ANALYSIS FOR ALL SOILS EXISTING AND IMPORTED INCLUDING BUT NOT LIMITED TO: EXISTING ON-SITE SOILS, IMPORTED TOPSOIL, LIME TREATED AREAS, AND ALL AMMENDMENTS. RECOMMENDATIONS FOR AMENDMENTS CONTAINED IN THIS ANALYSIS ARE TO BE CARRIED OUT BEFORE PLANTING OCCURS. PROVIDE 2 TESTS AT 6" DEPTH AND 2 TESTS AT 24" DEPTH THROUGHOUT THE SITE. PROVIDE ADDITIONAL TESTING (ONE 6" AND ONE 24" DEPTH TEST PER 25,000 SF FOR AREAS WHICH WERE LIME TREATED). EACH TEST SAMPLE SHALL CONTAIN 3 REPRESENTATIVE SOIL SAMPLES. ALL LIME TREATED PLANTING AREAS SHALL BE REMOVED AND REPLACED WITH IMPORT TOP SOIL AT NO COST TO THE OWNER. ALL TESTING SHALL BE PAID FOR BY THE CONTRACTOR. FOR BID PURPOSES AMEND ALL SOIL WITH 6 YARDS OMRI COMPOST 50LBS GYPSUM AND 100LBS OF GRO-POWER PLUS 5-3-1 W/ M PER 1000SF. CONTRACTOR TO SUBMIT ALL DELIVERY TICKETS FOR COMPOST AND FERTILIZERS FOR VERIFICATION.

- 2. ALL SOILS IMPORTED ONTO THE SITE FOR ANY PURPOSE SUCH AS GRADING, NON EXPANSIVE FILL, FILL, OR FOR ANY GENERAL PURPOSE MUST BE TESTED FOR PLANT SUITABILITY PRIOR TO PLACEMENT. ALL IMPORT SOILS SHALL BE NON-DETRIMENTAL TO PLANT MATERIAL AND SOILS ANALYSIS SUBMITTED TO THE LANDSCAPE ARCHITECT FOR REVIEW AND APPROVAL. PROVIDE I TEST PER 500 CY OF MATERIAL.
- 3. SOIL IS TO BE AMENDED, AT THE RATE INDICATED BY THE SOIL ANALYSIS, TO BRING THE SOIL ORGANIC MATTER CONTENT TO A MINIMUM OF 3.5% BY DRY WEIGHT, AND A MINIMUM OF 2" OF QUALITY RECYCLED COMPOST, ON ALL PLANTING AREAS.
- 4. ALL PLANTERS IN AREAS WHICH HAVE BEEN COMPACTED, SUCH AS ADJACENT TO BUILDINGS AND IN PARKING LOTS, SHALL BE CROSS RIPPED TO THE FOLLOWING DEPTHS: PLANTERS LESS THAN THREE (3) FEET WIDE SHALL HAVE COMPACTION RELIEVED TO A MINIMUM DEPTH OF TWENTY-FOUR (24) INCHES BELOW SUBGRADE. PLANTERS THREE TO TEN (3-10) FEET WIDE MUST HAVE COMPACTION RELIEVED TO A MINIMUM DEPTH OF 18" BELOW SUBGRADE, PLANTERS MORE THAN 10' WIDE SHALL HAVE COMPACTION RELIEVED TO A MINIMUM DEPTH OF 12" BELOW SUBGRADE. AREAS SHALL BE PROTECTED AFTER DECOMPACTION.
- 5. CONTRACTOR SHALL PERFORM A PERCOLATION TEST AT THE BEGINNING OF CONSTRUCTION AT I LOCATION PER ACRE (MAX OF 4) TO DETERMINE THE DRAINAGE CAPACITY OF THE EXISTING SITE SOIL FOR TREE HEALTH. NOTIFY THE LANDSCAPE ARCHITECT IF DRAINAGE IS LESS THAN 2" PER HOUR.

PLANTING NOTES (CONT)

SHRUBS, GROUNDCOVERS AND VINES

- I. GROUNDCOVER MUST BE PLANTED AS SHOWN ON THE PLAN, INCLUDING UNDER SHRUBS AND IN TREE WATERING BASINS.
- 2. SHRUBS AND PERENNIALS MUST HAVE ADEQUATE SETBACK FROM THE ADJACENT SIDEWALK AND EDGES OF PARKING LOT CURBS. NOTIFY LANDSCAPE ARCHITECT PRIOR TO INSTALLATION IF PLANT MATERIAL MAY PROTRUDE INTO THE PATH OF TRAVEL.

ACCESSORIES

- ALL PLANTING NOT BOUNDED BY CONCRETE OR A HARDSCAPE EDGE SHALL BE COMPLETELY SURROUNDED BY HEADERS.
- 2. ALL PLANTING AREAS MUST BE TOP-DRESSED WITH 3" LAYER OF RECYCLED CHIPPED MULCH. COLOR: BROWN. SUBMIT SAMPLE TO LANDSCAPE ARCHITECT FOR APPROVAL PRIOR TO ORDERING.
- 3. SEE SPECIFICATIONS FOR ALL FERTILIZER REQUIREMENTS

SUBMITTALS

- I. CONTRACTOR MUST SUBMIT ALL TESTS, PRODUCTS, ACCESSORIES, INCIDENTALS, CUT SHEETS OF ALL ITEMS SPECIFIED FOR REVIEW AND APPROVAL PRIOR TO INSTALLATION.
 - ALL PLANT MATERIAL MUST BE REVIEWED AND APPROVED BY THE LANDSCAPE ARCHITECT PRIOR TO DELIVERY. CONTRACTOR SHALL SUBMIT PHOTOS OF ALL SHRUBS, AND GROUND COVERS FOR PRELIMINARY REVIEW AND APPROVAL.
- 3. ALL SUBMITTALS AND PLANT MATERIAL NOT REVIEWED AND APPROVED IN WRITING BY THE LANDSCAPE ARCHITECT MAY BE SUBJECT TO FULL REMOVAL AND REPLACEMENT WITH APPROVED SOILS, FERTILIZERS, AND PLANT MATERIAL AT NO ADDITIONAL COST TO THE CONTRACT OR OWNER.

MUNICIPAL REQUIREMENTS

- I. ALL PLANT MATERIAL TO BE INSPECTED & APPROVED BY CITY REPRESENTATIVE AND LANDSCAPE ARCHITECT PRIOR TO INSTALLATION.
- DURING THE INSTALLATION OF LANDSCAPING AND INSTALLATION THE LANDSCAPE ARCHITECT MUST INSPECT AND MONITOR THE INSTALLATION OF MATERIALS TO VERIFY CONFORMANCE TO THESE PLANS. ONCE APPROVED, THE LANDSCAPE ARCHITECT SHALL PROVIDE A WRITTEN LETTER TO DEPARTMENT OF PLANNING AND DEVELOPMENT STATING COMPLIANCE WITH THE APPROVED PLANS.

PLANT SCHEDULE SAMLL PLANTING

HRUBS	BOTANICAL NAME	COMMON NAME	SIZE	WATER USE	SPACING	
	FESTUCA GLAUCA	BLUE FESCUE	I GAL	L	12" o.c.	
Т	NASSELLA TENUISSIMA	TEXAS NEEDLE GRASS	5 GAL	L	18" o.c.	
:	PENNISETUM SETACEUM	PURPLE FOUNTAIN GRASS	5 GAL	L	24" o.c.	

PLANTING LEGEND

SHRUB NAME SEE PLANT LIST
OUANTITY FOR ADDT'L INFO.

SHEET	TINDEX
Sheet Nu	umber Sheet Title
LANDSC	CAPE
LI	LANDSCAPE NOTES AND PLANT LIST
L2	PLANTING PLAN - TORRE AVENUE AT TOWN CENTER LANE
L3	CONSTRUCTION DETAILS
L4	IRRIGATION PLAN - TORRE AVENUE AT TOWN CENTER LANE
L5	IRRIGATION NOTES AND LEGEND
L6	IRRIGATION DETAILS
L7	IRRIGATION DETAILS
L8	IRRIGATION DETAILS



	Date: Scale: Designed: Drawn: Checked:							
								\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\
3	Proj. Engr: File:	\triangle	REVISIONS	DESIGN BY	DESIGN DATE	CITY APPR.	APPR. DATE	

IMPROVEMENT PLANS FOR

BIKE BOULEVARD IMPROVEMENTS - PHASE 1 LANDSCAPE NOTES AND PLANT LIST

CUPERTINO


FOR CITY OF CUPERTINO USE PROJECT # __2017-01.05 __ PUBLIC WORKS INSPECTOR: VOICE MAIL: REVIEWED BY:




CITY OF CUPERTINO

SHEET **29** OF **37**

CALIFORNIA








SHRUB PLANTING

SCALE: N.T.S.



which encircles the outer limits of the critical root zone(CRZ) of the tree to protect it from construction activity. The CRZ is calculated 1.25 feet times the diameter of the trunk measured in inches 4.5 feet above the natural grade).

2. All protective fencing shall be in place prior to commencement of any site work and remain in place until all exterior construction activity at the

3. Protective fencing shall be at least six (6) feet high, clearly visible, and shall have a tree protection sign affixed to the fence every twenty (20) feet in such a manner to be clearly visible and legible to workers on the site at a distance of twenty-five (25) feet. The sign(s) shall read "Tree Protection Zone Keep out".

4. The owner shall cause the required fencing and signage to be installed and maintained for the duration of the construction. 5. In situations where a protected tree remains in the immediate area of intended construction and the tree may be in danger of being damaged by construction equipment or other activity, the contractor or subcontractor shall protect the tree with 2"x4" lumber encircled with wire or other

means that do not damage the tree. The intent is to protect the trunk of the tree against incidental contact by large construction equipment. 6, Material Storage: No storage or placement of materials intended for use in construction or waste materials accumulated due to excavation or demolition shall be placed within the limits of the critical root zone of any protected tree. 7. Equipment Cleaning/Liquid Disposal: No equipment shall be cleaned or other liquids, including, without limitation, paint, oil, solvents, asphalt,

concrete, mortar or similar materials deposited or allowed to flow into the critical root zone of a protected tree. 8. Tree Attachments: No signs, wires or other attachments, other than those of a protective nature, shall be attached to any protected tree. 9. Vehicular Traffic: No vehicular and/or construction equipment traffic or parking shall take place within the critical root zone of any protected tree other than on existing street pavement.

10. No heavy equipment, including but not limited to trucks, tractors, trailers, bulldozers, excavators, skid steer tractors, trenchers, compressors, and hoists, shall be allowed inside the drip-line of any protected tree on any construction site. 11. Grade Changes: No grade changes shall be allowed within the limits of the critical root zone of any protected tree unless adequate protective

construction methods are approved in advance in writing by the city. 12. Impervious Paving: No paving with asphalt, concrete or other impervious materials shall be placed within the limits of the critical root zone of a protected tree, unless expressly permitted by the public works Dept


13. Root Pruning: All roots two inches or larger in diameter which are exposed as a result of trenching or other excavation shall be cut off square with a sharp medium tooth saw and covered with natural fiber burlap within two hours of initial exposure. 14. All public sidewalks shall remain open, free and clear for public access, unless closure is permitted by the Public Works Department.

TREE PROTECTION STANDARDS


CITY OF CUPERTINO STANDARD DETAILS APPROVED BY: _ DATE: 7/19/3


REVISED 5/13

TREE PROTECTION STANDARDS




COLORED CONCRETE BAND AT EXISTING CURB AND GUTTER









IMPROVEMENT PLANS FOR

BIKE BOULEVARD IMPROVEMENTS - PHASE 1 CONSTRUCTION DETAILS

CALIFORNIA

CUPERTINO

FOR CITY OF CUPERTINO USE PROJECT # <u> 2017-01.05</u> PUBLIC WORKS INSPECTOR: VOICE MAIL: REVIEWED BY:



CITY OF **CUPERTINO**

SHEET

31 OF **37**

CUPERTINO

CALIFORNIA

2. DO NOT WILLFULLY INSTALL THE SPRINKLER SYSTEM AS SHOWN ON THE DRAWINGS WHEN IT IS OBVIOUS IN THE FIELD THAT OBSTRUCTIONS, GRADE DIFFERENCES OR DIFFERENCES IN THE AREA DIMENSIONS EXIST THAT MIGHT NOT HAVE BEEN CONSIDERED IN THE ENGINEERING. SUCH OBSTRUCTIONS OR DIFFERENCES SHOULD BE BROUGHT TO THE ATTENTION OF THE OWNER'S AUTHORIZED REPRESENTATIVE. IN THE EVENT THAT THIS NOTIFICATION IS NOT PERFORMED, THE IRRIGATION CONTRACTOR SHALL ASSUME FULL RESPONSIBILITY FOR ANY REVISIONS NECESSARY.

3. IT IS THE RESPONSIBILITY OF THE IRRIGATION CONTRACTOR TO FAMILIARIZE HIMSELF WITH ALL GRADE DIFFERENCES, LOCATION OF WALLS, RETAINING WALLS, ETC. HE SHALL COORDINATE HIS WORK WITH THE GENERAL CONTRACTOR AND OTHER SUBCONTRACTORS FOR THE LOCATION AND THE INSTALLATION OF PIPE SLEEVES THROUGH WALLS, UNDER ROADWAYS, PAVING, STRUCTURES, ETC.

4. DUE TO THE SCALE OF THE DRAWINGS, IT IS NOT POSSIBLE TO INDICATE ALL OFFSETS, FITTINGS, SLEEVES, ETC., WHICH MAY BE REQUIRED. THE CONTRACTOR SHALL CAREFULLY INVESTIGATE THE STRUCTURAL AND FINISHED CONDITIONS AFFECTING ALL OF HIS WORK AND PLAN HIS WORK ACCORDINGLY, FURNISHING SUCH FITTINGS, ETC., AS MAY BE REQUIRED TO MEET SUCH CONDITIONS. DRAWINGS ARE GENERALLY DIAGRAMMATIC AND INDICATIVE OF THE WORK TO BE INSTALLED. THEN WORK SHALL BE INSTALLED IN SUCH A MANNER AS TO AVOID CONFLICTS BETWEEN IRRIGATION SYSTEMS. PLANTING. AND ARCHITECTURAL FEATURES.

5. VALVE LOCATIONS SHOWN ARE DIAGRAMMATIC. INSTALL IN GROUND COVER/SHRUB AREAS WHERE POSSIBLE (NOT IN LAWN AREA).

6. SPLICING OF 24 VOLT WIRES WILL NOT BE PERMITTED EXCEPT IN VALVE BOXES. LEAVE A 24" COIL OF EXCESS WIRE AT EACH SPLICE AND 100 FEET ON CENTER ALONG WIRE RUN. TAPE WIRE IN BUNDLES 10 FEET ON CENTER. NO TAPING PERMITTED INSIDE SLEEVES.

7. IRRIGATION CONTROL WIRES: SOLID STRAND COPPER WITH U.L. APPROVAL FOR DIRECT BURIAL IN GROUND, SIZE AWG-UF #14-1. COMMON GROUND WIRE: #12 WITH WHITE INSULATING JACKET. CONTROL WIRE: INSULATING JACKET OF COLOR OTHER THAN WHITE. SPLICES: MADE WITH 3M-DBY SEAL PACKS. EACH CONTROLLER SHALL HAVE ITS OWN INDEPENDENT GROUND WIRE.

8. NOTIFY ARCHITECT OF ANY ASPECTS OF LAYOUT WHICH WILL PROVIDE INCOMPLETE OR INSUFFICIENT WATER COVERAGE OF PLANT MATERIAL AND DO NOT PROCEED UNTIL HIS INSTRUCTIONS ARE OBTAINED.

9. INSTALL VALVE BOXES 12" FROM AND PERPENDICULAR TO WALK, CURB, BUILDING OR LANDSCAPE FEATURE. AT MULTIPLE VALVE BOX GROUPS, EACH BOX SHALL BE AN EQUAL DISTANCE FROM THE WALK, CURB, ETC. AND EACH BOX SHALL BE 12" APART. SHORT SIDE OF VALVE BOX SHALL BE PARALLEL TO WALK, CURB LAWN, ETC.

10. THE IRRIGATION SYSTEM DESIGN IS BASED ON THE MINIMUM OPERATING PRESSURE SHOWN ON THE IRRIGATION DRAWINGS. THE IRRIGATION CONTRACTOR SHALL VERIFY WATER PRESSURE PRIOR TO CONSTRUCTION. REPORT ANY DIFFERENCE BETWEEN THE WATER PRESSURE INDICATED ON THE DRAWINGS AND THE ACTUAL PRESSURE READING AT THE IRRIGATION POINT OF CONNECTION TO THE OWNER'S AUTHORIZED REPRESENTATIVE.


- 11. OPERATE IRRIGATION CONTROLLER(S) BETWEEN THE HOURS OF 10:00 PM AND 7:00 AM.
- 12. IRRIGATION CONTRACTOR TO NOTIFY ALL LOCAL JURISDICTIONS FOR INSPECTION AND TESTING OF INSTALLED BACKFLOW PREVENTION DEVICE.
- 13. PRIOR TO TRENCHING, CALL UNDERGROUND SERVICE ALERT, (1-800) 642-2444 FOR NORTHERN CALIFORNIA

14. ADJUSTING. CONTRACTOR SHALL INPUT ALL REQUIRED DATA INTO CONTROLLERS TO ALLOW SELF SCHEDULING INCLUSIVE OF PLANT SPECIES, PLANT WATER REQUIREMENTS, EXPOSURE, SOIL TYPE, SLOPE, IRRIGATION TYPE AND IRRIGATION EFFICIENCY.

15. THE APPLICANT SHALL SUBMIT AN IRRIGATION AUDIT REPORT WITH THE CERTIFICATE OF COMPLETION TO THE LOCAL AGENCY THAT MAY INCLUDE, BUT IS NOT LIMITED TO: INSPECTION, SYSTEM TUNE-UP, SYSTEM TEST WITH DISTRIBUTION UNIFORMITY, REPORTING OVERSPRAY OR RUN OFF THAT CAUSES OVERLAND FLOW, AND PREPARATION OF AN IRRIGATION SCHEDULE, INCLUDING CONFIGURING IRRIGATION CONTROLLERS WITH APPLICATION RATE, SOIL TYPES, PLANT FACTORS, SLOPE, EXPOSURE AND OTHER FACTORS NECESSARY FOR ACCURATE PROGRAMING. IRRIGATION AUDIT SHALL BE CONDUCTED BY A THIRD PARTY IRRIGATION AUDITOR. LANDSCAPE AUDITS SHALL NOT BE CONDUCTED BY THE PERSON WHO DESIGNED THE LANDSCAPE OR INSTALLED THE LANDSCAPE.

IRRIGATION LEGEND


SYMBOL	MODEL NUMBER	DESCRIPTION	PSI	GPM	RADIUS			
	RGP-418-10	IRRIGATION INSIDE DASHED OUTLINE AREA: TORO DL2000 DRIP EMITTER TUBING PART NUMBER: RGP-218-10 0.50 GPH EMITTERS 18" ON CENTER DRIPLINE PIPE WITH TORO TRI-LOC FITTINGS (OR APPROVED EQUAL) INSTALLED 4" COVER BELOW SOIL LEVEL. INSTALL DRIPLINE PER INSTALLATION DETAILS	30	1.0 GPH	_			
*-09	SEE DETAILS	PIPE CONTINUATION SYMBOL AFTER CONTROL VALVE AND FILTER ASSEMBLY FOR DRIP TUBING, TYPICAL. REFER TO DRIP TUBING PIPE CONFIGURATION DETAILS.	SUBSUR	FACE				
F	T-FCH-H	TORO FLUSH VALVE INSIDE 10" ROUND BOX INSTALLED PER INSTALLATION DETAILS.						
(AV)	T-YD-500	TORO AIR VACUUM RELIEF VALVE INSIDE 10" ROUND BOX INSTALLED AT HIGH POINT WITHIN LANDSCAPE PER INSTALLATION DETAILS.						
(P)	T-DL-MP9	TORO OPERATION INDICATOR INSTALLED WITHIN EACH LANDSCAPE PLANTER PER INSTALLATION DETAILS.						
0	1-1201-1151-8130 PMR-MF-30-1"	AMIAD 1" FILTER WITH 130 MESH SCREEN WITH SENNINGER 1" IN-LINE PRESSURE REDUCING VALVE						
•	P-220-26 SERIES	TORO REMOTE CONTROL VALVE						
•	EXISTING P-220 SERIES	TORO REMOTE CONTROL VALVE						
×	EXISTING	EXISTING BACKFLOW PREVENTOR						
W	EXISTING	EXISTING WATER METER						
C-1 - 1" 15 -		STATION NUMBER GALLONS PER MINUTE VALVE SIZE						
		EXISTING MAINLINE: SCHEDULE 40 PVC PLASTIC PIPE WITH SCHEDULE 40 PVC SWELD FITTINGS. 18" COVER.	SOLVENT					
		EXISTING LATERAL: CLASS 200 PVC PLASTIC PIPE WITH SCHEDULE 40 PVC SOLVENT WELD FITTINGS. 12" COVER.						
		MAINLINE: SCHEDULE 40 PVC PLASTIC PIPE WITH SCHEDULE 40 PVC SOLVENT WELD FITTINGS. 18" COVER.						
		LATERAL LINE: 1120-CLASS 200 PVC PLASTIC PIPE WITH SCHEDULE 40 PVC SOLVENT WELD FITTINGS. 12" COVER.						
		1120-SCHEDULE 40 PVC SLEEVES WITH SCHEDULE 40 PVC FITTINGS REFER TO FOR MORE INFORMATION. 24" COVER	CIVIL PI	_ANS				



IMPROVEMENT PLANS FOR

BIKE BOULEVARD IMPROVEMENTS - PHASE 1 IRRIGATION NOTES AND LEGEND

FOR CITY OF CUPERTINO USE PROJECT # <u>2017-01.05</u> PUBLIC WORKS INSPECTOR: VOICE MAIL: REVIEWED BY:




CITY OF **CUPERTINO L5**


33 OF **37**


SHEET

CALIFORNIA CUPERTINO

CONTRACTOR AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SIT SAFETY OF ALL PERSONS AND PROPERITY. THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY SHALL DEPEND, INDEMNEY AND HOLD THE OWNER AND THE ENGINEER HARMLESS FROM ANY AND ON THIS PROJECT. EXCEPTING FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER







TRENCH WIDTH


TOP OF EXISTING


A.C. PAYING-

TYPICAL COMBINATION TRENCH


DIG MODEL DSPI-12 OPERATION INDICATOR

SLEEVE TRENCH UNDER EXISTING ROADWAY









IMPROVEMENT PLANS FOR

CALIFORNIA

BIKE BOULEVARD IMPROVEMENTS - PHASE 1 IRRIGATION DETAILS

CUPERTINO

FOR CITY OF CUPERTINO USE PROJECT # <u>2017-01.05</u> PUBLIC WORKS INSPECTOR: VOICE MAIL: REVIEWED BY:




CITY OF **CUPERTINO** SHEET **34** OF **37** NOTE: LOCATE STAPLES ALONG TUBING AT 36" ON CENTER AND AT ALL FITTINGS (TEES, ELLS, ETC.) (1) FINISH GRADE. (2) TOPSOIL TO FINISH GRADE ③ TORO DL2000 PLASTIC LOCATOR STAKE (IPS1500). 4 TORO DL2000 DRIPLINE (5) SUBGRADE NATIVE SOIL

TOPSOIL TO FINISH GRADE - SUBGRADE NATIVE SOIL



SECTION






ELEVATION

 $\boxed{}$ 1 $\boxed{}$ 1 above finish grade.

6 4" DEPTH OF TUBING PER LEGEND

- 2 FINISH GRADE.
- 3 TORO DL2000 FLUSH VALVE(FCH-H-FHT).
- TORO TRI-LOC X 3/4" MHT ADAPTER (FJA16).
- 5 TORO POLY TUBING
- 6 POLY PIPING.
- 7 CARSON 910 GREEN 10" ROUND PLASTIC VALVE BOX. HEAT BRAND "FV" ON LID IN 1" HIGH CHARACTERS.
- (8) TORO TRI-LOC ELL (FEE16).
- (9) BRICK SUPPORTS (2 COMMON BRICKS REQUIRED).
- (1) NATIVE SOIL PER SPECIFICATIONS.
- (1) PEA GRAVEL SUMP $(6" \times 18")$.

FLUSH VALVE CONNECTION TO PE TUBING




1 1" ABOVE FINISH GRADE. 2) FINISH GRADE.

3 CARSON 910 GREEN 10" LOCKING ROUND PLASTIC VALVE BOX. HEAT BRAND "AV" ON LID IN 1" HIGH CHARACTERS.

(4) TORO DL2000 AIR/VACUUM RELIEF VALVE (YD-500-34).

- (5) TORO TRI-LOC X 1/2" FPT TEE (FTF16).
- 7) PEA GRAVEL SUMP (6"
- (8) BRICK SUPPORTS (2) COMMON BRICKS REQUIRED).
- 9 NATIVE SOIL PER SPECIFICATIONS.

AIR/VACUUM RELIEF VALVE CONNECTION TO PE TUBING



- 1) PVC LATERAL LINE FROM CONTROL VALVE.
- (2) PVC SUPPLY MANIFOLD.
- (3) PVC TEE (SxSxS).
- (4) PVC ELL (SxS).
- (5) TORO TRI-LOC ELL (FEE16).
- 6) TORO TRI-LOC TEE (FTT16).
- 7) TORO BLUE STRIPE POLY TUBING AT SUPPLY AND FLUSH END OF EACH ISLAND.
- (8) TORO TRI-LOC TEE X 1/2" SLIP ADAPTER (FTV16).
- 9 TORO DL2000 AIR/VACUUM RELIEF VALVE (YD-500-34) PLUMBED TO TUBING AT HIGH
- 10 TORO DL2000 DRIPLINE LATERAL
- 1) TORO DL2000 AUTOMATIC FLUSH VALVE PLUMBED TO FLUSH MANIFOLD AT LOW POINT.
- DIG MODEL DSPI-12 OPERATION INDICATOR WITH 1/2" MPT THREADS CONNECTED TO LÁTERAL LINE INSTALLED AT THE EDGE OF THE LANDSCAPE NEAR THE CONTROL VALVE
- (13) ISLAND PERIMETER.
- PERIMETER LATERALS 2" TO 4" FROM EDGE.
- (15) CONTROL VALVE.
- TYPICAL ISLAND MANIFOLD

NOT TO SCALE

1. ASSEMBLE AND INSTALL FILTER, REMOTES CONTROL VALVE AND PRESSURE REGULATING VALVE ASSEMBLIES ACCORDING TO DETAILS.

2. ASSEMBLE AND INSTALL SUPPLY HEADERS ACCORDING TO DETAIL. TAPE OR PLUG OPEN CONNECTIONS TO PREVENT DEBRIS CONTAMINATION.

3. ASSEMBLE AND INSTALL EXHAUST HEADERS IN ACCORDANCE WITH DETAILS. TAPE OR PLUG ALL OPEN CONNECTIONS TO PREVENT DEBRIS CONTAMINATION.

4. INSTALL DRIP LATERALS. TAPE OR PLUG OPEN ENDS WHILE INSTALLING TO PREVENT DEBRIS CONTAMINATION.

5. INSTALL AIR VACUUM RELIEF VALVES AT HIGHEST POINTS OF THE IRRIGATION ZONES IN ACCORDANCE WITH DETAILS.

6. THOROUGHLY FLUSH DRIPLINE LATERALS AND CONNECT TO EXHAUST HEADERS OR INTERCONNECTING LATERALS WHILE FLUSHING.

7. THOROUGHLY FLUSH EXHAUST HEADERS AND INSTALL LINE FLUSHING VALVES ACCORDING TO DETAILS.

8. THOROUGH FLUSHING OF EACH INSTALLATION SEGMENT IS NECESSARY TO ENSURE THAT NO DEBRIS CONTAMINATION OCCURS.

9. LOCATE AND INSTALL CHECK VALVE(S) AS NEEDED AND AS SHOWN IN INSTALLATION

10. SEE IRRIGATION NOTES, LEGEND/SPECIFICATIONS FOR ADDITIONAL INFORMATION.

11. ALL TREES TO BE PLANTED WITHIN CENTER OF DRIP LINE RUNS

12. BURY DRIPLINE 4" BELOW GRADE AND STAKE EACH 36" O.C. LOCATED AT EMITTER AND AS NECESSARY TO INSURE SECURITY.

13. ALL FITTINGS TO BE USED WILL BE PER MANUFACTURERS SPECIFICATION. COMPRESSION FITTINGS OR APPROVED EQUAL.

14. THE TOTAL LENGTH OF ALL INTERCONNECTED DRIP LINE SHALL NOT EXCEED THE MAXIMUM RUN LENGTH. SEE TORO SUBSURFACE IRRIGATION DESIGN GUIDE

DRIPLINE SUBGRADE INSTALLATION NOTES



DESIGN DESIGN CITY APPR. DATE REVISIONS

IMPROVEMENT PLANS FOR

BIKE BOULEVARD IMPROVEMENTS - PHASE 1 IRRIGATION DETAILS

CUPERTINO

CALIFORNIA

FOR CITY OF CUPERTINO USE PROJECT # <u>2017-01.05</u>


PUBLIC WORKS INSPECTOR: VOICE MAIL: REVIEWED BY:

CITY OF **CUPERTINO**

SHEET

35 OF **37**





(1) FINISH GRADE.

② 4" DEPTH OF TUBING PER LEGEND

(3) DEPTH OF PVC SUPPLY MANIFOLD PER LEGEND

4 PVC CROSS (SxSxSxS).

5 TORO DL2000 COMPRESSION

ADAPTER (CA-710). 6 PVC TEE (SxSxS).

7 TORO DL2000 DRIPLINE LATERAL

8 PVC SUB-MANIFOLD.

9 PVC TEE (SxSxS).

10 PVC SUPPLY MANIFOLD FROM DRIP ZONE KIT.

AIR VACUUM RELIEF VALVE LOCATION

① FINISH GRADE.

② 4" DEPTH OF TUBING PER LEGEND

③ PVC CROSS (SxSxSxS).

(4) TORO DL2000 COMPRESSION ADAPTER (CA-710).

(5) TORO DL2000 DRIPLINE LATERAL

6 TORO BLUE STRIPE POLY TUBING (T-EHP-1645) SUB MANIFOLD LENGTH

AS NECESSARY

⑦ CARSON 910 GREEN 10" ROUND PLASTIC LOCKING VALVE BOX WITH AIR RELIEF VALVE





1 FINISH GRADE.

② TORO DL2000 DRIPLINE LATERAL

3 TORO TRI-LOC ELL OR TEE

(4) TORO BLUE STRIPE POLY TUBING (T-EHP-1645) LENGTH AS NECESSARY

5 TORO TRI-LOC X 1/2" MPT ADAPTER (FAM16).


6 PVC TEE (SxSxT) WITH 1/2" FPT OUTLET.

7 NATIVE SOIL BACKFILL PER SPECIFICATIONS.

(8) 4" DEPTH OF TUBING PER LEGEND

(9) DEPTH OF PVC SUPPLY LINE PER LEGEND

DRIPLINE TO PVC INSTALLATION



1 FINISH GRADE.

TORO DL2000 DRIPLINE LATERAL

③ TORO TRI-LOC TEE (FTT16).

(4) TORO BLUE STRIPE POLY TUBING

5 TORO TRI-LOC X 1/2" MPT ADAPTER (FAM16).

6 PVC TEE (SxSxT) WITH 1/2" FPT OUTLET.

7 NATIVE SOIL BACKFILL PER SPECIFICATIONS.

(8) 4" DEPTH OF TUBING PER LEGEND

9 DEPTH OF PVC SUPPLY LINE PER SPECIFICATIONS.

CUPERTINO

DRIPLINE TO PVC INSTALLATION



\ \	Date:						//	/
)	Scale:						REGISTRE	\$ ^{\(\varphi\)}
)	Designed:						S	;/ <u>-</u>
.	Drawn:							
1	Checked:						\\\$	3
33	Proj. Engr:	DEV//CIONIC	DESIGN	DESIGN DATE	CITY APPR.	APPR. DATE		3
n	File:	REVISIONS	BY	DATE	APPR.	DATE		

IMPROVEMENT PLANS FOR

BIKE BOULEVARD IMPROVEMENTS - PHASE 1 IRRIGATION DETAILS

CALIFORNIA

FOR CITY OF CUPERTINO USE PROJECT # <u>2017-01.05</u>	
PUBLIC WORKS INSPECTOR:	
VOICE MAIL:	
REVIEWED BY:	15T
NAME DATE	

CITY OF **CUPERTINO**

SHEET **36** OF **37**

In the Santa Clara Valley, storm drains flow directly to our local creeks, and on to San Francisco Bay, with no treatment.

Storm water pollution is a serious problem for wildlife dependent on our waterways and for the people who live near polluted streams or baylands.

Proper management of construction sites reduces pollution significantly.

This sheet summarizes the "Best Management Practices" (BMPs) for storm water pollution prevention.

ORDINANCE OF THE CITY OF CUPERTINO FOR STORM WATER POLLUTION PREVENTION & WATERCOURSE PROTECTION: Chapter 9.18

9.18.040 Discharge into the storm drain prohibited

It is unlawful to cause, allow, or permit to be discharged, any discharge not composed entirely of stormwater to the storm drain system or to surface waters or to any location where it would contact or eventually be transported to surface waters, including flood plain areas, unless specifically called out in the Municipal Regional Permit as an exempt or conditionally exempt discharge.

9.18.070 Accidental Discharge

All persons shall notify the Director of Public Works immediately upon accidentally discharging pollutants of concern to enable countermeasures to be taken by the City to minimize damage to storm drains and the receiving waters. Initial notification shall be followed, within five (5) business days of the date of occurrence, by a detailed written statement describing the causes of the accidental discharge and the measures being taken to prevent future occurrences. Such notification will not relieve persons of liability for violations of this chapter or for any fines imposed on the City on account thereof under Section 13350 of the California Water Code, or for violation of Section 5650 of the California Fish and Wildlife Code, or any other applicable provisions of State or Federal laws.

9.18.220 Violation

Any person who violates any provision of this Chapter shall be guilty of a misdemeanor and upon conviction thereof shall be punished as provided in Chapter 1.12 of the City of Cupertino Municipal Code.

Chapter 1.12: General Penalty, Section 1.12.010, paragraph D, states*:

Unless otherwise specified by this code, an infraction is punishable by:

A fine not to exceed \$100 for a first violation A fine not to exceed \$200 for a second violation

A fine not to exceed \$500 for a third violation of the same chapter within one year.

9.18.240 Civil penalty for illicit discharges*

Any person who discharges pollutants, in violation of this Chapter, by the use of illicit connections shall be civilly liable to the City in a sum not to exceed twenty-five thousand dollars per day per violation for each day in which such

*Excerpts - For complete CODE language refer to the City of Cupertino Municipal Code.

> **Building Dept:** 408-777-3228 Public Works Dept: 408-777-3354 Santa Clara County Recycling Hotline: 800-533-8414 www.reducewaste.org www.recyclestuff.com Small Business Hazardous Waste: 408-299-7300 Cupertino Sanitary Sewer Distr 408-253-7071 Santa Clara Valley Urban Runoff Pollution Prevention Prgm 800-794-2482 State Office of Emergency Services 1-800-852-7550 (24 hrs) Report spills to 911

General Construction and Site Supervision

Storm Drain Pollution from Construction Activities

Construction sites are common sources of storm water pollution. Materials and wastes that blow o wash into a storm drain, gutter, or street have a frect impact on local creeks and the Bay. As a contractor, or site supervisor, owner or operator of a site, you may be responsible for any environmental damage caused by your subcontractors or employees.

General Principles

- Keep an orderly site and ensure good. housekeeping practices are used.
- Maintain equipment properly. Cover materials when they are not in use.
- drains and drainage channels.

Keep materials away from streets, storm

- Ensure dust control water doesn't leave site or discharge to storm drains. Advance Planning To Prevent Pollution
- Schedule excavation and grading activities for dry weather periods. To reduce so i erosion, plant temporary vegetation or place other erosion controls before rain begins. Use the Erosion and Sediment Control Manual available from the Regional Water Quality Control Board, as a reference.
- Control the amount of runoff crossing your site (especially during excavation!) by using berns or temporary or permanent drainage dtches to divert water flow around the site Reduce stormwater runoff velocities by constructing temporary check dams or berms
- where appropriate Train your employees and subcontractors: The city can provide brochure's about these issues for you to distribute to workers at your construction site. Inform your subcontractors about the stormwater requirements and their own responsibilities. Use Bluepant for a Clear Bay, a construction best management ractions guide available at our Building Dept. counter.

Good Housekeeping Practices

- Designate one area of the site for auto parking. vehicle refueling, and routine equipment maintenance. The designated area should be well away from streams or storm drain inlets, berined if necessary. Make major repairs off site. To prevent off-site tracking of dirt, provide. entrances with stabilized aggregate surfaces. Or
- provide a tire wash area. Keep materials out of the rain - prevent runoff contamination at the source. Cover exposed piles of soil or construction materials with plastic sheeting or temporary roofs. Before it rains, sweep and remove materials from surfaces that drain to storm drains, creeks, or channels.
- Contain all litter, food wrappers, bottles and cans - Place lidded trash and recycling bins around the site.
- Clean up leaks, drips and other spills immediately so they do not contaminate soil or groundwater or leave residue on paived surfaces. Use dry cleanup methods whenever possible. If you must use water use just enough to keep the
- dumpate is under roofs or cover with tarps or plastic sheeting secured around the outside of the dumpster. Never clean out a dumpster by hosing it. down on the construction site.

Cover and maintain dumpsters. Pace

- Place portable toilets away from storm drains. Make sure portable toilets are in good working order. Check requently for leaks:
- Materials/Waste Handling ☐ Practice Source Reduction -- mormize waste. when you order materials. Estimate carefully:
- Recycle excess materials, whenever possible such as concrete, asphalt, scrap metal, solvents, degreasers, cleared vegetation, paper, rock, and ve higle maintenaince materials such as used oil. artifeeze batteries, and tires:
- Dispose of all wastes properly. Materials that cannot be recycled must be taken to an appropriate landfill or disposed of as hazardous waste. Neverbury waste materials or leave them in the street or near a creek or stream bed.
- In addition to local grading and building permits, you will need to obtain coverage under the State's General Construction Activity Stormwater Permit in your construction site's disturbed area totals 5 acres or more. Information on the General Permit
- can be obtained from the Regional Water Quality Control Board. (This criteria will change to one the street

Landscaping, Gardening, and Pool Maintenance

Lands caping/Garden Maintenance

- toxic to aquatic life. Protect stockpiles and landscaping materials from wind and rain by storing them under
- Schedule grading and excavation projects. during dry weather
- Use temporary check dams or ditches to divert runoff away from storm drains.

tarps or secured plastic sheeting.

- Protect storm drains with sandbags, gravelfilled bags, straw wattles, or other sedment
- Re-vegetation is an excellent form of erosion. control for any site Store pesticides, fertilizers, and other
- chemicals indoors or in a shed or storage Use pesticides sparingly, according to instructions on the labe. Rinse empty

containers, and use rinsewater as produc

trash. Dispose of unused pesticides as

Dispose of rinsed, empty containers in the

In Cupertino, residents with curbside recycling. can collect lawn, garden and tree trimmings in yardwaste toters. Yardwaste will be collected and composted by the city's contractors. Residents are encouraged to compost yardwaste on-site themselves. Or take

yardwaste to a landfill where it will be

- composted Landscape contractors should take clippings and pruning waste to a landfill that composts yard waste (BFI's Newby Island and Zanker Rd. landfill are the nearest)
- Do not blow or rake leaves into

Storm Drain Pollution from Landscaping and Swimming Pool Maintenance

increase the likelihood that earth and garden chemicals will run off into the storm drains during irrigation or when it rains. Swimming pool water containing chlorine and copper-based algaecides should never be discharged to storm drains. These chemicals are

Many landscaping activities expose soils and

Pool/Fountain/Spa Maintenance

Draining pools or spas

When it's time to drain a pool, spa, or fountain please be sure to call the Cupertino Sanitary District before you start for further guidance on flow rate restrictions, backflow prevention, and handling special cleaning waste (such as acid wash). Discharge flows should be kept to the low levels typically possible through a garden hose Higher flow rates may be prohibited by local ordinance.

- ☐ Never discharge pool or spa water to a street or storm drain; discharge to a sanitary sewer cleanout
- If possible, when emptying a pool or spla, let chlorine dissipate for a few days and then recycleireuse water by draining it gradually onto a landscaped area.
- Do not use copper-based algaecides. Controllaigae with chlorine or other alternatives, such as sodium bromide. Fifter Cleaning
- Never clean a filter in the street or near a storm drain. Rinse cartridge and diatomaceous earth filters onto a dirt area. and spade fifter residue into soil. Dispose of spent diatomaceous earth in the garbage.
- ☐ If there is no suitable dirt area, call Cupertino Sanitary for instructions on discharging filter backwash or rinsewater to the sanitary sewer.


Earth-Moving Activities

Storm Drain Pollution from Earth-Moving Activities

Soil excavation and grading operations loosen large amounts of soil that can flow or blow into storm crains when handled improperly. Sediments in runoff can dog storm drains, smother aquatic life, and cestroy habitats in creeks and the Bay. Effective erosion control practices reduce the amount of runof crossing a site and slow the flow with check dams or roughened ground surfaces.

Practices During Construction

- Remove existing vegetation only when absolutely necessary Plant temporary vegetation for erosion control on slopes or where construction is not immediately planned.
- ☐ Protect downslope drainage courses, streams, and storm drains with wattles, or temporary drainage swales. Use check dams or ditches to divert runoff around excavations. Refer to the Regional Water Quality Control Board's Erosion and Sediment Control Field Manual for proper erosion and sediment control measures
- Cover stockpiles and excavated soil with secured tarps or plastic sheeting



Dewatering Operations

Storm Drain Pollution From Dewatering Activities

Be sure to call your city's storm water inspector at 408-472-9907 before discharging water to a street, gutter, or storm drain. Filtration or diversion through a basin, tank, and sediment trap may be required. Reuse water for dust control irrigation or another on-site purpose to the greatest extent

Check for Sediment or Toxic Pollutants

- Check for odors, discoloration, or an oily sheen on ground water.
- Ask your city inspector whether the groundwater must be tested by a certified
- Depending on the test results, you may be allowed to discharge pumped groundwater to the storm drain OR you may be required to discharge to the sanitary sewer or collect and haul the water off-site for treatment and disposal at an appropriate treatment facility.
- When discharging to a storm drain, protect the inlet using a barrier of burlap bags filled with drain rock, or cover inlet with filter fabric anchored under the grate.
- Contact Cupertino Sanitary District at 253-7071 prior to discharging to the sanitary sewer.

The Project Contractor is responsible

located within the Public Right of Way

for removal of all BMP Facilities

upon project final inspection.

Heavy Equipment Operation

Storm water Pollution from Heavy Equipment on Construction Sites

Poorly maintained vehicles and heavy equipment that leak fuel, oil, antifreeze or other fluids on the construction site are common sources of storm drain pollution Prevent spills and leaks by isolating equipment from runoff channels, and by watching for leaks and other maintenance problems. Remove construction equipment from the site as soon as possible.

Site Planning and Preventive Vehicle Maintenance

- Designate one area of the construction site, well away from stream s or storm drain intels, for auto and equipm entiparking refueling, and routine vehicle and equipment maintenance. Contain the area with berms, sand bags, or other
- Maintain all vehicles and heavy equipment.
- 2 Perform major maintenance, repair jobs and vehicle and equipment washing off-site, where
- If you must orain and replace motoroil, radiator coolant, or other fluids on site, use drip pans or drop cloths to catch drips and spills. Collect all spent fluids, store in separate containers, and properly dispose as hazardous waste (recycle
- Do not use diesel oil to lubricate equipment. parts, of clean equipment. Use only water for any onsite cleaning.
- Cover exposed fifth wheel hitches and other oily or greaty equipment during rain events.

Spill Cleanup

Clean up spills im mediately.

- A Neverhose down "dirty" pavement or impermeable surfaces where fluids have spilled Use dry cleanup methods (absorbent materials, cat litter, and/or rags) whenever possible and properly dispose of absorbent
- 2 Sweep up spilled dry materials immediately. Never aftempt to "wash them away" with water.
- I Use as little water as possible for dust control. Ensure water used doesn't leave sitt or
- ☐ Clean up spills on dirtareas by digging up and properly disposing of contaminated soil Call 911 for significant spills
- If the spill poses a significant hazard to human health and safety, properly or the environment, you must also report it to the State Office of Emergency Services.

The property owner and the contractor share ultimate responsibility for the activities that occur on a construction site. You may be held responsible for any environmental damage caused by your subcontractors or employees.

Painting and Application of Solvents and Adhesives

Storm Drain Pollution from Paints,

Solvents, and Adhesives All paints, solvents, and adhesives contain chemicals that are harmful to wildlife in local creeks, San Francisco Bay, and the Pacific Ocean. Toxic chemicals may come from liquid or solid products or from cleaning residues or rags. Paint material and wastes, adhesives and cleaning fluids should be recycled when possible, or disposed of properly to prevent these materials from flowing into storm drains and watercourses.

Handling Paint Products

☐ Keep all liquid paint products and wastes away from the gutter, street, and storm

Painting Cleanup

- ☐ Never clean brushes or rinse paint containers into a street, gutter, storm drain, French drain, or creek.
- For water-based paints, paint out brushes to the extent possible, and rinse into an inside sink drain that goes to the sanitary sewer. For oil-based paints, paint out brushes to the

extent possible and clean with thinner or

solvent. Filter and reuse trinners and solvents,

where possible. Dispose of excess liquids and

residue às hazardous waste. When thoroughly dry, empty paint cans, used brushes, rags, and drop doths may be disposed of as garbage

Paint Removal

- Paint chips and dust from non-hazardous dry stripping and sand blasting may be swept up or collected in plastic drop cloths and disposed of as trash.
- Chemical paint stripping residue, and chips and dust from marine paints, or paints containing lead, mercury or tributyl tin must be disposed of as hazardous wastes. Lead based paint removal requires a state-certified contractor.
- When stripping or cleaning building exteriors with high-pressure water, block storm drains. Direct washwater onto a dirt area and spade into soil. Or, check with Cupertino Sanitary District to find out if you can mop or vacuum the washwater and dispose of it in a sanitary sewer drain. Sampling of the washwater may be required.
- ☐ Washwater from painted buildings constructed before 1978 can contain high amounts of Lead, even if paint chips are not present. Before you begin stripping paint or cleaning pre-1978 building exteriors with water under high pressure, test paint for lead by taking paint scrapings to a local laboratory. (See Yellow Pages for a state-certified
- If there is loose paint on the building, or if the paint tests positive for lead, block storm drains. Check with Cupertino Sanitary District. to determine whether you may discharge water to the sanitary sewer, or if you must send it. offsite for disposal as hazardous waste.

Paint Disposal, Return or Donation

- Dispose of unwanted liquid paint, thinners. solvents, glues, and deaning fluids as hazardous waste (call the Small Business Hazardous Waste Prgm: 299-7300).
- Or Return to supplier. (Unopened cans of paint may be able to be returned. Check with the

vendor regarding its "buy-back" policy.)

Donate excess paint (call 299-7300 to donate.)

Roadwork and Paving

- General Business Practices ☐ Develop and implement erosion/sediment control plans for roadway embankments.
- Schedule excavation and grading work during
- Check for and repair leaking equipment Perform major equipment repairs at designated areas in your maintenance yard where cleanup is easier. Avoid performing equipment repairs at construction sites.
- ☐ When refueling or when vehicle/equipment maintenance must be done on site, designate a location away from storm drains and creeks:
- Do not use diesel oil to lubricate equipment parts or clean equipment. Recycle used oil, concrete, broken asphalt, etc. whenever possible, or dispose of properly.

(www.recyclestuff.com for list of recycling

Asphalt/Concrete Removal

companies.)

- Avoid creating excess dust when breaking asphalt or concrete.
- After breaking up old pavement, be sure to remove all chunks and pieces. Make sure broken pavement does not come in contact with rainfall or runoff.
- ☐ When making saw cuts, use as little water as possible. Shovel or vacuum saw-cut slurry and remove from the site. Cover or protect storm drain inlets during saw-cutting. Sweep up, and properly dispose of, all residues.

Sweep, never hose down streets to clean up

tracked dirt. Use a street sweeper or vacuum truck. Do not dump vacuumed liquor in storm

Storm Drain Pollution from Roadwork

Road paving, surfacing, and pavement removal happen right in the street where there are numerous opportunities for a sphalt, saw-cut slurry, or excavated material to illegally enter storm drains. Extra planning is required to store and dispose of materials properly and guard against pollution of storm drains, creeks, and the Bay

During Construction

- Avoid paving and seal coating in wet weather, or when rain is forecast, to prevent fresh materials from contacting stormwater
- Cover and seal catch basins and manholes when applying seal coat, slurry seal, fog seal, or similar materials. Protect drainage ways by using earth dikes.
- sand bags, or other controls to divert or trap and filter runoff ☐ Never wash excess material from exposedaggregate concrete or similar treatments into

a street or storm drain. Collect and recycle, or

dispose to dirt area. Cover stockpiles (asphalt, sand, etc.) and other construction materials with plastic tarps. Protect from rainfall and prevent runoff with temporary roofs or plastic sheets and berms

Park paving machines over drip pans or

drips when not in use. ☐ Clean up all spills and leaks using "dry" methods (with absorbent materials and/or rags), or dig up, remove, and properly dispose of contaminated soil.

absorbent material (cloth, rags, etc.) to catch

Collect and recycle or appropriately dispose of excess abrasive gravel or sand. ??? Avoid over-application by water trucks for dust

Fresh Concrete and Mortar Application -

Storm Drain Pollution from Fresh Concrete and Mortar Applications

Fresh concrete and cement-related mortars that wash into lakes, streams, or estuaries are toxic to fish and the aquatic environment. Disposing of these materials to the storm drains or creeks can block storm drains, causes serious problems, and

- Wash out concrete mixers only in designated washout areas in your yard, away from storm drains and waterways, where the water will flow into a temporary waste pit in a dirt area. Let water percolate through soil and dispose of settled, hardened concrete as garbage. Whenever possible, recycle washout by
- and away from storm drains or waterways. Protect dry materials from wind. Secure bags of cement after they are open. Be sure to keep wind-blown cement powder away from streets, gutters, storm drains,
- concrete forms, tools, or trailers.

During Construction

- Don't mix up more fresh concrete or cement than you will use in a two-hour period.
- Set up and operate small mixers on tarps or heavy plastic drop cloths ☐ When cleaning up after driveway or sidewalk construction, wash fines onto dirt areas, not
- down the drive way or into the street or storm Protect applications of fresh concrete and mortar from rainfall and runoff until the
- material has dried ☐ Wash down exposed aggregate concrete only when the washwater can (1) flow onto a dirt area. (2) drain onto a bermed surface from which it can be pumped and disposed of properly, or (3) be vacuumed from a catchment created by blocking a storm drain inlet. If necessary, divert runoff with temporary berms.
- Make sure run off does not reach gutters or storm drains. When breaking up pavement, be sure to pick up all the pieces and dispose of properly Recycle large chunks of broken concrete. See www.reducewaste.org for info on recyclers...
- ☐ Never bury waste material. Dispose of small amounts of excess dry concrete, grout, and mortar in the trash.

☐ Never dispose of washout into the street.

storm drains, drainage ditches, or streams

Small Business Hazardous Waste

Disposal Prgm Businesses that generate less than 27 gallons or 220 pounds of hazardous waste per month are eligible to use this program. Call 408-299-7300

for a quote.





UPDATED SEPTEMBER 2016

is prohibited by law.

- General Business Practices
- pumping back into mixers for reuse. Wash out chutes onto dirt areas that do not flow to streets or drains:

under cover, protected from rainfall and runoff

Always store both dry and wet materials

- ☐ Do not use diesel fuel as a lubricant on

rainfall, and runoff



